

AD-A156 416


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
PEQUANKEET POWDER COMP. (U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV JUN 80


1/2

UNCLASSIFIED

F/G 13/13

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

AD-A156 416

SACO RIVER BASIN
CONWAY, NEW HAMPSHIRE

**PEQUAWKET POWER
COMPANY DAM**

NH 00322

NHWRB NO. 52.02


**PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM**



**DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154**

JUNE 1980

DMC FILE COPY



85 06 17 021

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NH 00322	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Pequawket Power Company Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		8. CONTRACT OR GRANT NUMBER(s)
9. PERFORMING ORGANIZATION NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		12. REPORT DATE June 1980
		13. NUMBER OF PAGES 82
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Saco River Basin Conway, New Hampshire Pequawket		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) -The dam is a concrete stop log spillway structure located between earthen abutments. It is 45 ft. long with a maximum height of 15.5 ft. There are no gates or other operating facilities incorporated into this dam. It is considered to be in fair condition. The dam is intermediate in size with a significant hazard potential. The test flood ranges from 1/2 PMF to the PMF. There are various remedial measures which should be implemented by the owner.		

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

PEQUAWKET POWER COMPANY DAM
NH 00322
NHWRB 52.02

Accession For		
NTIS GRA&I	<input checked="" type="checkbox"/>	
DTIC TAB	<input type="checkbox"/>	
Unannounced	<input type="checkbox"/>	
Justification		
By		
Distribution/		
Availability Codes		
Dist	Avail and/or Special	
A/1	23	CNN

SACO RIVER BASIN
CONWAY, NEW HAMPSHIRE



PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

**NATIONAL DAM INSPECTION PROGRAM
PHASE I - INSPECTION REPORT
BRIEF ASSESSMENT**

Identification No: NH 00322
Name of Dam: Pequawket Power Company Dam
Town: Conway
County and State: Carroll, New Hampshire
Stream: Pequawket Brook
Date of Inspection: June 9, 1980

The Pequawket Power Company Dam is a concrete stoplog-spillway structure located between earthen abutments. The dam is approximately 15.5 feet high from the channel bottom at the toe of the dam to the top of the training walls with an overall length of nearly 45 feet. The spillway measures about 36.8 feet between concrete training walls with a 2 feet thick concrete pier located in the center providing two openings, each about 17.4 feet long. These openings are each divided into three stoplog bays by vertical 12-inch wide I-beams which hold the stoplogs in place. These four vertical stanchion beams are each held in place by a pin at the top attaching them to the concrete service bridge. Removal of these pins would allow the stanchion beams to pivot and fall into the downstream channel, thereby providing a greater cross-sectional area available for discharge. There are no gates or other operating facilities incorporated into this dam.

The dam impounds water from Pequawket Brook and Page Randall Brook. The spillway discharge flows in a northerly direction about 0.5 miles to its confluence with the Swift River. The dam was originally constructed to generate electricity for adjoining mills, but was rebuilt to serve recreational purposes. The pond is 1.29 miles in length with a surface area of about 143 acres. The maximum storage capacity at top of dam is about 1,880 acre-feet.

As a result of the visual inspection of this facility, the dam is considered to be in FAIR condition. Major concerns are: minor seepage through the split stone wall located behind the left training wall; a longitudinal crack in the left span of the concrete service bridge; erosion of both concrete training walls at the downstream toe of the dam; and the general lack of surface erosion protection on both abutments.

This dam is classified as INTERMEDIATE in size and a SIGNIFICANT hazard structure in accordance with the recommended guidelines established by the Corps of Engineers. The test flood for this dam, therefore, ranges from one-half the

Probable Maximum Flood (1/2 PMF) to the Probable Maximum Flood (PMF). Since the dam falls on the lower end of the intermediate size range, the 1/2 PMF was utilized for this hydrologic analysis. The test flood inflow was estimated to be 18,400 cfs and resulted in a routed test flood outflow equal to 14,100 cfs which would overtop the dam crest by about 4.3 feet. The maximum spillway capacity with the water level at the dam crest and the "typical" arrangement of stoplogs (eight per bay) in place was estimated to be 1,780 cfs, or about 13 percent of the routed test flood outflow. An assumed breach with the water surface at the dam crest would cause an increase of about 1 foot in the downstream prefailure tailwater, bringing the water surface to a point approaching the sill of the restaurant supply business located near the right abutment of the dam. The potential for economic loss would exist.

It is recommended that the owner engage a qualified registered engineer to investigate the seepage through the split stone wall located behind the left training wall; investigate the longitudinal crack in the left span of the concrete service bridge; investigate the erosion of the concrete training walls at the toe of the dam; specify erosion protection for the soil abutments at both ends of the dam; and perform a detailed hydrologic-hydraulic investigation to assess further the potential of overtopping the dam and the need for and the means to increase project discharge.

The recommendations and remedial measures are described in Section 7 and should be addressed by the owner within one year after receipt of this Phase I Inspection Report.



Kenneth M. Stewart

Kenneth M. Stewart
Project Manager
N.H.P.E. 3531

S E A Consultants Inc.
Rochester, New Hampshire

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and

rarity of such a storm event, finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

The Phase I investigation does not include an assessment of the need for fences, gates, no-trespassing signs, repairs to existing fences and railings and other items which may be needed to minimize trespassing and provide greater security for the facility and safety to the public. An evaluation of the project for compliance with OSHA rules and regulations is also excluded.


TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
Letter of Transmittal	i
Brief Assessment	ii
Review Board Page	iv
Preface	v
Table of Contents	vii
Overview Photo	ix
Location Map	x
1. PROJECT INFORMATION	1-1
1.1 General	1-1
1.2 Description of Project	1-1
1.3 Pertinent Data	1-3
2. ENGINEERING DATA	2-1
2.1 Design	2-1
2.2 Construction	2-1
2.3 Operation	2-1
2.4 Evaluation	2-1
3. VISUAL INSPECTION	3-1
3.1 Findings	3-1
3.2 Evaluation	3-2
4. OPERATIONAL AND MAINTENANCE PROCEDURES	4-1
4.1 Operational Procedures	4-1
4.2 Maintenance Procedures	4-1
4.3 Evaluation	4-1

<u>Section</u>	<u>Page</u>
5. EVALUATION OF HYDROLOGIC/HYDRAULIC FEATURES	5-1
5.1 General	5-1
5.2 Design Data	5-1
5.3 Experience Data	5-1
5.4 Test Flood Analysis	5-1
5.5 Dam Failure Analysis	5-1
6. EVALUATION OF STRUCTURAL STABILITY	6-1
6.1 Visual Observations	6-1
6.2 Design and Construction Data	6-1
6.3 Post-Construction Changes	6-2
6.4 Seismic Stability	6-2
7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES	7-1
7.1 Dam Assessment	7-1
7.2 Recommendations	7-1
7.3 Remedial Measures	7-2
7.4 Alternatives	7-2

APPENDICES

APPENDIX A - INSPECTION CHECKLIST	A-1
APPENDIX B - ENGINEERING DATA	B-1
APPENDIX C - SELECTED PHOTOGRAPHS	C-1
APPENDIX D - HYDROLOGIC AND HYDRAULIC COMPUTATIONS	D-1
APPENDIX E - INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS	E-1



OVERVIEW PHOTO - PEQUAWKET POWER COMPANY DAM





Fig. 1

Pequawket Power
Co. Dam

LOCATION PLAN

2 0 2 4
Scale in Miles

**NATIONAL DAM INSPECTION PROGRAM
PHASE I INSPECTION REPORT
PEQUAWKET POWER COMPANY DAM**

**SECTION 1
PROJECT INFORMATION**

1.1 General

a. Authority. Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. S E A Consultants Inc. has been retained by the New England Division to inspect and report on selected dams in the state of New Hampshire. Authorization and notice to proceed were issued to S E A Consultants Inc. under a letter of November 5, 1979 from William Hodgson Jr., Colonel, Corps of Engineers. Contract No. DACW33-80-C0008 has been assigned by the Corps of Engineers for this work.

b. Purpose

(1) To perform technical inspection and evaluation of non-federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-federal interests

(2) To encourage and prepare the states to initiate quickly effective dam safety programs for non-federal dams

(3) To update, verify and complete the National Inventory of Dams

1.2 Description of Project

a. Location. The Pequawket Power Company Dam is located in the town of Conway, New Hampshire at the north end of Pequawket Pond, immediately downstream of the NH Route 16 bridge (Main Street Bridge) in Conway, New Hampshire. The dam impounds water from Pequawket Brook and Page Randall Brook. The spillway discharge flows in a northerly direction approximately 0.5 miles to its confluence with the Swift River. The dam is shown on U.S.G.S. Quadrangle, Ossipee Lake, New Hampshire, with coordinates approximately at N43°58'43", W70°07'16", Carroll County, New Hampshire (See Location Plan).

b. Description of Dam and Appurtenances. Pequawket Power Company Dam is a concrete stoplog-spillway structure located between earthen abutments and is primarily an extension of a highway culvert. The dam is approximately 15.5 feet high from the channel bottom at the toe of the dam to the top of the training walls with an overall length of nearly 45 feet. The spillway measures about 36.8 feet between concrete training walls with a 2 feet thick concrete pier located in the center providing two openings, each about 17.4 feet long. These openings are

each divided into three stoplog bays by vertical 12-inch wide I-beams which hold the stoplogs in place. Thus, there are a total of six stoplog bays with a total effective weir length of 30.8 feet. The pier and training walls are constructed on top of a 20 feet wide concrete apron which extends the entire width of the channel bottom. The height from the top of the concrete apron to the top of the training walls is 12 feet. The downstream channel is covered with riprap which extends about 12 feet downstream from the edge of this concrete apron. A concrete service bridge, 4 feet wide and 18 inches thick, connects the pier and training walls above the stoplog bays. A split stone retaining wall runs perpendicular to the left training wall and terminates somewhere within the left earth abutment.

c. Size Classification. Intermediate (height - 15.5 feet; storage - 1880 acre-feet) based on storage (greater than or equal to 1,000 acre-feet and less than 50,000 acre-feet), as given in the Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification. Significant Hazard. The discharge resulting from an assumed failure of the Pequawket Power Company Dam would cause an increase of about 1 foot in the downstream prefailure tailwater, bringing the water surface to a point approaching the sill of the restaurant supply business located near the right abutment. The potential for economic loss would exist.

e. Ownership. The original dam was owned by the Pequawket Power Company. In 1961, ownership was transferred to the state of New Hampshire, Water Resources Board, 37 Pleasant Street, Concord, New Hampshire 03301. Telephone No. (603) 271-3406.

f. Operator. The dam is maintained and operated by the state of New Hampshire Water Resources Board, Vernon A. Knowlton, Chief Engineer, 37 Pleasant Street, Concord, New Hampshire 03301. Telephone No. (603) 271-3406.

g. Purpose of Dam. The dam was originally constructed to generate electricity for adjoining mills. The dam has been rebuilt and it presently serves recreational purposes.

h. Design and Construction History. It is not known when the original dam was built, but records on file at the state of New Hampshire Water Resources Board indicate that the dam washed out in 1922 and was rebuilt in 1923 as a wood "A" frame structure with split stone training walls. Extensive repairs were made to the wood members in 1952. Reconstruction of the dam in its present configuration was begun in 1969 and completed in 1970. The structure was designed by the state of New Hampshire Water Resources Board and was built by the state of New Hampshire Fish and Game Department. The design plans indicate the concrete dam is reinforced and built partially on earth and partially on the split stone remains of the previous dam that occupied this site. A set of design plans are on file at the state of New Hampshire Water Resources Board. No in-depth design calculations were found.

i. Normal Operating Procedures. The Pequawket Power Company Dam is used for the retention of Pequawket Pond, which is used for recreational purposes. The New Hampshire Water Resource Board owns and operates the dam. The normal operating procedure is described in detail in Section 4.1a.

1.3 Pertinent Data.

a. Drainage Area. The drainage area above Pequawket Power Company Dam covers approximately 27.2 square miles (nearly 17,400 acres), consisting predominantly of steeply sloping terrain surrounding numerous ponds and swampy areas which drain to the dam. The topography in the drainage basin ranges from over 2,000 feet (NVGD) at White Ledge Mountain to approximately 452.5 feet (NGVD) at the base of the dam. The majority of the basin is heavily wooded and generally undeveloped. The major concentrations of development which do exist are located near the center of Conway, adjacent to Route 16 and near lakes and ponds in the area. This development consists of both year-round and seasonal housing, as well as associated commercial and industrial development.

b. Discharge at Damsite. Discharge at the damsite occurs over the stoplog spillway. The invert of the permanent spillway crest (top of concrete apron) is set at an elevation of 452.5 feet (NGVD). The spillway measures about 36.8 feet between the training walls, with a 2 feet thick concrete pier dividing the spillway into two 17.4 feet long sections. These sections are each divided into three stoplog bays by vertical 12-inch wide I-beams. The six stoplog bays provide a total effective weir length of 30.8 feet. The eight (8) stoplogs that were installed in each bay ("typical" stoplog arrangement) resulted in a crest elevation of 457.3 feet (NGVD) and maintain a ponding elevation of about 458 feet behind the dam. The vertical I-beams are attached to the service bridge with removable pins and the bases of these beams are set into slots in the permanent concrete spillway crest. Consequently, when the pins at the top are removed the I-beams will pivot and fall into the downstream channel, thereby providing a greater cross-sectional area available for discharge.

- (1) Outlet works (conduits) - N/A
- (2) Maximum known flood at damsite - unknown
- (3) The ungated spillway capacity with eight stoplogs in place and the water surface at the top of the dam (Elevation 464.5 feet) was estimated to be 1,780 cfs.
- (4) The ungated spillway capacity with eight stoplogs in place the water surface at the test flood elevation (Elevation 468.8 feet) was estimated to be 3,420 cfs.
- (5) Gated spillway capacity at normal pool elevation - N/A

(6) Gated spillway capacity at test flood elevation - N/A

(7) The total spillway capacity at the test flood elevation (Elevation 468.8 feet) with eight stoplogs in place was estimated to be 3,420 cfs.

(8) The total project discharge at the top of the dam (Elevation 464.5 feet) with eight stoplogs in place was estimated to be 1,780 cfs.

(9) The total project discharge at the test flood elevation (Elevation 468.8 feet) with eight stoplogs in place was estimated to be 14,100 cfs.

c. Elevation (Feet NGVD) based on an elevation 458.0 shown on U.S.G.S. quad sheet assumed to be pool elevation at top of design stoplog elevation (nine stoplogs in place).

(1) Streambed at toe of dam - 449

(2) Bottom of cutoff - unknown

(3) Maximum tailwater - unknown

(4) Normal pool - 458

(5) Full flood control pool - N/A

(6) Spillway crest - 452.5 permanent crest (top of concrete apron)
457.3 "typical" stoplog arrangement

(7) Design surcharge (Original Design) - unknown

(8) Top of dam - 464.5

(9) Test flood surcharge - 468.8

d. Reservoir (Length in feet)

(1) Normal pool - 6,800

(2) Flood control pool - N/A

(3) Spillway crest pool - 6,625

(4) Top of dam - 7,325

(5) Test flood pool - 7,335

e. Storage (acre-feet)

- (1) Normal pool - 290
- (2) Flood control pool - N/A
- (3) Spillway crest pool - 198
- (4) Top of dam - 1,880
- (5) Test flood pool - 3,130

f. Reservoir Surface (acres)

- (1) Normal pool - 143
- (2) Flood control pool - N/A
- (3) Spillway crest - 122
- (4) Test flood pool - 410
- (5) Top of dam - 335

g. Dam

(1) Type - concrete stoplog spillway structure between earthen embankments

- (2) Length - 45 feet
- (3) Height - 15.5 feet
- (4) Top width - N/A
- (5) Side Slopes - upstream slope, N/A; downstream slope, 2.0V to 1.0H
- (6) Zoning - unknown
- (7) Impervious Core - unknown
- (8) Cutoff - Reinforced concrete, depth unknown
- (9) Grout curtain - none
- (10) Other - none

h. Diversion and Regulating Tunnel

Not Applicable (See Section j)

i. Spillway

- (1) Type - concrete with wood stoplogs
- (2) Length of weir - 6 stoplogs bays with effective weir length of 30.8 feet
- (3) Crest elevation - 452.5 (permanent crest, top of concrete apron)
457.3 ("typical" stoplog arrangement)
- (4) Gates - N/A

(5) U/S Channel - The channel immediately upstream from the spillway consists of a bridge opening which measures approximately 25 feet wide by 11 feet deep to the channel bottom. The sides of the bridge opening were constructed of split stone masonry with mortared joints. The bottom appeared to consist of the natural stream bed. It appears that this opening would not severely restrict the flow through the spillway. Upstream from the bridge opening the channel is wide and unobstructed. The slopes appear to be stable.

(6) D/S Channel - The spillway discharges into a natural stream channel below the dam. The bottom of the channel is covered with boulders and cobbles. Trees overhang the channel on both sides, but the channel is generally wide and unobstructed.

j. Regulating Outlets

- (1) There are no regulating outlets.

SECTION 2 ENGINEERING DATA

2.1 Design

A set of plans dated 1969 showing plan, elevation, and section for the reconstruction of the dam are available at the state of New Hampshire Water Resources Board. No in-depth engineering calculations, as-built drawings, or specifications were found.

2.2 Construction

No construction records are available for use in evaluating the dam. Records from the state of New Hampshire Water Resources Board indicate reconstruction of the dam began in late 1969 by the state of New Hampshire Fish and Game Department and was completed in early 1970.

2.3 Operation

No engineering operational data were found.

2.4 Evaluation

a. Availability. Reconstruction of the Pequawket Power Company Dam was designed by the state of New Hampshire Water Resources Board. Other than the plans described above, no additional engineering data were found to be available.

b. Adequacy. The lack of in-depth engineering data did not allow for a definitive review. Therefore, the adequacy of this dam could not be assessed from the standpoint of reviewing design and construction data, but is based primarily on visual inspection, past performance history and sound engineering judgment.

c. Validity. The field investigation indicated that the external features of the Pequawket Power Company Dam substantially agree with those shown on the furnished plans. The only apparent difference is that on the day of inspection, 4.8 feet of stoplog were in place, not 5.5 feet as shown on Sheet No. 1 "Elevation of Pier" Detail.

It should be noted that on page 3 of the plans, all changes in details and dimensions to "Elevation East Abutment", "Sidewalk Joint Detail", and "Typical Stanchion Beam" Detail encircled and labeled with the word "out" refer to details apparently removed for Horn Pond Dam. These details apparently continue to apply to Pequawket Power Company Dam. Visual inspection confirmed the existence of the sidewalk joint and the handrail. It was not possible to confirm the reinforcing steel configuration.

SECTION 3 VISUAL INSPECTION

3.1 Findings

a. General. The Pequawket Power Company Dam impounds a pond of intermediate size. The watershed above the dam consists predominately of steeply sloping terrain surrounding numerous ponds and swampy areas which drain to the dam. The drainage basin is heavily wooded and generally undeveloped, except for the perimeter of the lakes and ponds in the area, the Route 16 corridor, and the downtown Conway area. The downstream area is predominately undeveloped.

The field inspection of Pequawket Power Company Dam was made on June 9, 1980. The inspection team consisted of personnel from S E A Consultants Inc. and Geotechnical Engineers, Inc. Inspection checklists, completed during the visual inspection, are included in Appendix A. At the time of inspection, 4.8 feet of stoplogs were in place and water was passing approximately 5 inches deep over the spillway. The pool elevation was at approximately 457.7 NGVD. The upstream face of the dam could only be inspected above this water level.

b. Dam. Pequawket Power Company Dam is a concrete stoplog spillway structure located between earthen abutments. The dam is approximately 15.5 feet high from the channel bottom at the toe of the dam to the top of the training walls with an overall length of nearly 45 feet. The spillway measures about 36.8 feet between concrete training walls with a 2 feet thick concrete pier located in the center providing two openings, each about 17.4 feet long. These openings are each divided into three stoplog bays by vertical 12-inch wide I-beams which hold the stoplogs in place. Thus, there are a total of six stoplog bays with a total effective weir length of 30.8 feet (See Photo No. 2). The pier and training walls are constructed on top of a 20 feet wide concrete apron which extends the entire width of the channel bottom. The height from the top of the concrete apron to the top of the training walls is 12 feet. The downstream channel is covered with riprap which extends about 12 feet downstream from the edge of this concrete apron. A concrete service bridge, 4 feet wide and 18 inches thick, connects the pier and training walls above the stoplog bays (See Photo No. 3). A split stone retaining wall runs perpendicular to the left training wall and terminates somewhere within the left earth abutment (See Photo No. 4).

It appears that the training walls of the concrete stoplog-spillway were poured directly against the stone-masonry training walls at the ends of the dam that previously occupied this site. The concrete apron on the bottom of the structure appears to have been poured directly on top of concrete and stone rubble, which apparently is also the remains of the previous dam. No signs of instability of the concrete-and-stone rubble foundation or of the original stone-masonry training walls were observed at the time of the inspection.

It appears that the foundation under the concrete and split stone is soil. Minor seepage was discharging from the split stone retaining wall that runs perpendicular to the left training wall and terminates in the left abutment (See Photo No. 5).

A longitudinal crack has developed in the top of the left span of the concrete service bridge near the downstream edge. The location of this crack coincides with the location of a 10-inch I-beam embedded in the downstream edge of the service bridge (See Plans and Details in Appendix B).

Some erosion of the concrete training walls has taken place on the downstream toe of the dam where it joins the concrete apron (See Photo No. 6).

There is soil fill between the ends of the concrete stoplog-spillway structure and the abutments. At the left abutment, there has been some erosion of this fill, apparently due to runoff from an adjacent parking lot (See Photo No. 4). Brush and small trees are growing on this fill. At the right abutment, no evidence of erosion was observed, but there is little grassy vegetation to prevent erosion if the dam should be overtopped. Some brush is growing on this fill. There is a wooden building about 20 feet from the end of the concrete stoplog-spillway structure on the right abutment. The concrete foundation wall of this building comprises the right bank of the channel for a distance of about 50 feet downstream from the dam (See Photo No. 7).

There were two logs and an old tire in the water behind the stoplogs. There were five large logs on the concrete apron downstream of the stoplogs (See Photo No. 2).

c. Appurtenant Structures. There are no appurtenant structures incorporated into this dam.

d. Reservoir Area. The slopes of the reservoir appear to be stable. No evidence of significant sedimentation was observed. The approach channel to the dam is slightly constricted by the opening under the highway bridge immediately upstream of the dam, but is wide and unobstructed upstream of the bridge. There are no trees overhanging the approach channel for a distance of a few hundred feet upstream from the dam.

e. Downstream Channel. The bottom of the downstream channel is covered with boulders and cobbles. Trees overhang both sides of the channel, but the channel is wide and unobstructed. As noted above, there were five large logs on the spillway apron immediately downstream of the stoplogs.

3.2 Evaluation

On the basis of the results of the visual inspection, Pequawket Power Company Dam is considered to be in fair condition.

Minor seepage through the split stone wall at the left abutment could cause internal erosion in the abutment soil if not corrected.

A longitudinal crack in the left span of the concrete service bridge coinciding with the location of a 10-inch I-beam embedded in the service bridge could result in failure of the stoplog support structure. The 10-inch I-beam anchors the top of the 12-inch wide stanchion beams which hold the stoplogs in place. Further propagation of this crack could cause failure of the I-beam embedment which would result in the failure of the stanchion beams and thus failure to support the stoplogs.

Erosion of the concrete training walls at the downstream toe of the dam, which if continued, could effect the stability of the training walls.

Some surface erosion of the soil on the downstream side of the left abutment could result in breaching through that abutment if not corrected.

The general lack of surface erosion protection on both abutments makes the abutments susceptible to erosion if the dam should be overtopped.

A minor amount of debris collected on the upstream side of the stoplogs could trap other debris and reduce the spillway capacity.

Brush and small trees growing on the left abutment and brush growing on the right abutment could cause a seepage and erosion problem as they grow larger, if a tree blows over and pulls out its roots, or if a tree dies or is cut and its roots rot.

SECTION 4 OPERATIONAL AND MAINTENANCE PROCEDURES

4.1 Operational Procedures

a. General. The Pequawket Power Company Dam is used for the retention of Pequawket Pond. The normal operating procedure for this dam during the summer months is to have a dam operator from the New Hampshire Water Resource Board visit the dam about 2 to 3 times per month and report gage readings back to the main office of the New Hampshire Water Resource Board in Concord. Engineers at the main office, in turn, direct any manipulation of stoplogs necessary to regulate the storage or release of water in order to maintain the seasonal pond level at elevation 457.5 feet \pm (NGVD).

The operating procedure for the winter months is to draw down the pond after November 1. This is accomplished by removing all stoplogs from two bays and removing two stoplogs in each of the remaining four bays. All stoplogs are replaced after spring runoff.

Emergency operating procedures consist of removing as many stoplogs as possible during flood conditions and, if the dam is threatened, pulling the four pins and allowing the stanchions supporting the stoplogs to fall into the downstream channel. Conditions that would require pulling the pins have not occurred to date.

It should be noted that, according to the operational log kept by the dam operator for the New Hampshire Water Resource Board, few, if any, visits are made to the dam by the operator between the time that stoplogs are removed in November and replaced in the spring (See Appendix B, Operational Log).

b. Description of Any Warning System in Effect. No written warning system exists for the dam.

4.2 Maintenance Procedures

a. General. The owner, the New Hampshire Resource Board, is responsible for the maintenance of the dam. The maintenance procedure for this dam is to have the dam operator visually inspect the dam while performing normal operating procedures (See Section 4.1a). As a result of these visits, dam maintenance is performed on an as-needed basis.

b. Operating Facilities. There are no operating facilities incorporated into this dam.

4.3 Evaluation

The current operational and maintenance procedures for the Pequawket Power Company Dam are inadequate to insure that all problems encountered can be remedied within a reasonable period of time. The owner should continue with the present operational and maintenance procedure of visiting the dam 2 to 3 times per month in the summer. In addition, the owner should perform inspections at least once a month in the winter, as well as establish a warning system to follow in event of flood flow conditions or imminent dam failure.

SECTION 5 EVALUATION OF HYDROLOGIC/HYDRAULIC FEATURES

5.1 General. Pequawket Power Company Dam consists of a concrete stoplog-spillway structure located between earthen abutments. The dam is approximately 15.5 feet high from the channel bottom at the toe of the dam to the top of the training walls with an overall length of nearly 45 feet. The spillway measures about 36.8 feet between concrete training walls with a 2 feet thick concrete pier located in the center providing two openings, each about 17.4 feet long. These openings are each divided into three stoplog bays by vertical 12-inch wide I-beams which hold the stoplogs in place. Thus, there are a total of six stoplog bays with a total effective weir length of 30.8 feet. Immediately upstream from the dam is a highway bridge opening which measures approximately 25 feet wide by 11 feet high. It appears that this culvert would not represent a severe upstream flow restriction.

The drainage area consists of predominantly steeply sloped terrain surrounding numerous ponds and swampy areas in the upper part of the basin. Consequently, stormwater deposited in the upper portions of the drainage area would be intercepted by these ponds and swampy areas before flowing to the dam. The dam is classified as intermediate in size, having a maximum storage of 1880 acre-feet.

5.2 Design Data. No hydrological or hydraulic design data were disclosed.

5.3 Experience Data. No experience data were disclosed. Maximum flood flows or elevations are unknown.

5.4 Test Flood Analysis. Due to the absence of detailed design and operational information, the hydrologic evaluation was performed utilizing data gathered during field inspection, watershed size and an estimated test flood determined from the Corps of Engineers guide curves. For this dam (intermediate size and significant hazard), the test flood ranges from one-half the Probable Maximum Flood (1/2 PMF) to the full Probable Maximum Flood (PMF). The 1/2 PMF was selected for the analysis since the dam falls to the lower end of the intermediate size range. The drainage area consists predominantly of steeply sloping terrain. However, since numerous ponds and swampy areas are located in the upper portions of the basin, the "rolling" curve from the Corps of Engineers set of guide curves was used to estimate the maximum probable flood peak flow rate.

Based on an estimated maximum probable flood peak flow rate of 1,350 cfs per square mile and a drainage area of 27.2 square miles, the test flood inflow was estimated to be 18,400 cfs. The test flood was routed through the reservoir in accordance with the Corps of Engineers procedure for Estimating Effect of Surcharge Storage on Maximum Probable Discharge. The reservoir water surface was assumed to be at an elevation of approximately 458 feet (NGVD) prior to the flood routing. The routed test flood outflow was estimated to be 14,100 cfs. This analysis indicated that the dam crest would be overtopped by 4.3 feet. The maximum spillway capacity with the water level at the dam crest and the "typical" arrangement of stoplogs in place (eight) was estimated to be 1,780 cfs, which is only about 13 percent of the routed test flood outflow. The maximum spillway capacity with the water level at the dam crest and all stoplogs and stanchion beams removed was estimated to be 4,600 cfs, which is only about 33 percent of the routed test flood outflow, and the dam crest would be overtopped by 4 feet under these conditions.

5.5 Dam Failure Analysis. The impact of dam failure was assessed utilizing the "Rule of Thumb" Guidance for Estimating Downstream Failure Hydrographs published by the Corps of Engineers. The analysis covered a reach extending approximately 600 feet downstream. The prefailure discharge with the water surface at the dam crest is significant, so prefailure tailwater conditions were included in the hydrologic calculations and the dam failure analysis was conducted with the water surface at the dam crest. Under these conditions, it was determined that the routed dam failure discharge would significantly increase the hazard over the prefailure discharge tailwater. Based on this analysis, the Pequawket Power Company Dam has been classified as a significant hazard.

A breach width of 17.4 feet, which is nearly 40 percent of the total length of the dam and coincides with the length of one spillway section (three stoplog bays), and a failure of height of about 12 feet were used to determine the failure discharge. This discharge, combined with flow over the unfailed portion of the spillway, yielded a total failure discharge of 2,110 cfs. Discharge just prior to an assumed breach was estimated to be about 1,780 cfs.

An assumed failure of the dam would cause an increase of about 1 foot in the downstream prefailure tailwater, bringing the water surface to a point approaching the sill of the restaurant supply business located near the right abutment of the dam. The potential for economic loss would exist. Further downstream the channel profile widens and the stage of the failure discharge reduces significantly.

SECTION 6 EVALUATION OF STRUCTURAL STABILITY

6.1 Visual Observations

The visual observations indicate the following potential structural problems:

- a. Minor seepage through the split stone wall located behind the left training wall could cause internal erosion in the abutment soil if not corrected.
- b. A longitudinal crack in the left span of the concrete service bridge coinciding with the location of a 10-inch I-beam embedded in the service bridge. This I-beam anchors the top of the 12-inch wide stanchion beams which hold the stoplogs in place. Further propagation of this crack could cause failure of the I-beam embedment which would result in the failure of the stanchion beams and thus failure to support the stoplogs.
- c. Erosion of both concrete training walls at the downstream toe of the dam which, if continued, could affect the stability of the training walls.
- d. Some surface erosion of the soil on the downstream side of the left abutment which could result in breaching through that abutment if not corrected.
- e. General lack of surface erosion protection on both abutments which makes the abutments susceptible to erosion if the dam should be overtopped.
- f. Brush and small trees growing on the left abutment and brush growing on the right abutment which could cause a seepage and erosion problem as they grow larger if a tree blows over and pulls out its roots, or if a tree dies or is cut and its roots rot.

6.2 Design and Construction Data

No information regarding the original design or construction of the dam was found.

6.3 Post-Construction Changes

In 1969, the wood "A" frame dam, with split stone training walls, was replaced with a reinforced concrete structure. The majority of the stone which comprised the old dam was left in place and the new concrete structure was cast integrally with the existing stone.

6.4 Seismic Stability

This dam is located in Seismic Zone 2 and, in accordance with the Phase I guidelines, does not warrant seismic analysis.

SECTION 7 ASSESSMENT, RECOMMENDATIONS, AND REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition. The visual examination indicates that Pequawket Power Company Dam is in fair condition. The major concerns with respect to the integrity of the dam are:

- (1) Minor seepage through the split stone wall located behind the left abutment
- (2) A longitudinal crack in the left span of the concrete service bridge coinciding with the location of a 10-inch I-beam embedded in the service bridge which anchors the top of stanchion beams that hold the stoplogs in place
- (3) Erosion of the concrete training walls at the toe of the dam
- (4) Surface erosion on the downstream side of the left abutment
- (5) Lack of erosion protection on both the left and right abutments which consist of soil
- (6) Brush and small trees growing on the left abutment and brush growing on the right abutment

b. Adequacy of Information. The information available from the visual inspection and the hydraulic computations is adequate to identify the problems mentioned in 7.2. These problems will require the attention of a registered professional engineer qualified in the design and construction of dams who will have to make additional engineering studies to design or specify remedial measures. No additional information is needed for the purposes of this Phase I investigation.

c. Urgency. The owner should implement the recommendations in 7.2 and 7.3 within one year after receipt of this Phase I report.

7.2 Recommendations

The owner should retain a registered professional engineer qualified in the design and construction of dams to:

- (1) Investigate the seepage through the split stone wall located behind the left training wall and design remedial measures if needed.

- (2) Investigate the longitudinal crack in the left span of the concrete service bridge coinciding with the location of a 10-inch beam embedded in the service bridge and design remedial measures if necessary.
- (3) Investigate the erosion of the concrete training walls at the toe of the dam and specify remedial measures if necessary
- (4) Specify repairs for the erosion that has occurred on the downstream side of the left abutment
- (5) Specify erosion protection for the soil abutments at both ends of the dam
- (6) Perform a detailed hydrologic-hydraulic investigation to assess further the potential of overtopping the dam and the need for and the means to increase project discharge.

The owner should implement the recommendations made by the engineer.

7.3 Remedial Measures

a. Operating and Maintenance Procedures. The owner should:

- (1) Remove trees and brush and associated root systems from abutments
- (2) Continue with the present dam inspections 2 to 3 times per month in the summer as well as performing inspections at least once a month in the winter
- (3) Engage a registered professional engineer qualified in the design and construction of dams to make a comprehensive technical inspection of the dam once every year
- (4) Establish a surveillance program for use during and immediately after periods of heavy rainfall, establish written procedures to be followed during flooding periods, and also establish a formal downstream warning program to follow in case of emergency

7.4 Alternatives

There are no practical alternatives to the recommendations of Section 7.2 and 7.3

APPENDIX A
INSPECTION CHECKLIST

INSPECTION CHECK LIST
PARTY ORGANIZATION

PROJECT: Pequawket Power Co. Dam, NH

DATE: June 9, 1980

TIME: 9:45 a.m.

WEATHER: Sunny, cool

W.S. ELEV. 457.7 **U.S.** 449.8 **DN.S.**
(NGVD)

PARTY:

1. Kenneth Stewart, S E A
2. Bruce Pierstorff, S E A
3. Robert Durfee, S E A
4. Philip Upton, S E A
5. Ronald Hirschfeld, GEI

6. _____
7. _____
8. _____
9. _____
10. _____

PROJECT FEATURE	INSPECTED BY	REMARKS
1. <u>Structural Stability</u>	<u>K. Stewart/R. Durfee</u>	
2. <u>Hydrology/Hydraulics</u>	<u>B. Pierstorff/P. Upton</u>	
3. <u>Soils and Geology</u>	<u>R. Hirschfeld</u>	
4. _____	_____	_____
5. _____	_____	_____
6. _____	_____	_____
7. _____	_____	_____
8. _____	_____	_____
9. _____	_____	_____
10. _____	_____	_____

INSPECTION CHECK LIST

PROJECT: Peguawket Power Co. Dam, NH DATE: June 9, 1980
 PROJECT FEATURE: Dam Embankment NAME: _____
 DISCIPLINE: _____ NAME: _____

AREA EVALUATED

CONDITIONS

DAM EMBANKMENT

Crest Elevation	464.5
Current Pool Elevation	457.7
Maximum Impoundment to Date	Unknown
Surface Cracks	Minor hairline cracks in several concrete surfaces
Pavement Condition	Not paved
Movement or Settlement of Crest	None observed
Lateral Movement	None observed
Vertical Alignment	Good
Horizontal Alignment	Good
Condition at Abutment and at Concrete Structures	Some erosion of both concrete training walls at downstream toe
Indications of Movement of Structural Items on Slopes	None observed
Trespassing on Slopes	No evidence observed
Vegetation on Slopes	Brush and small trees on downstream side of left abutment; brush on downstream side of right abutment
Sloughing or Erosion of Slopes or Abutments	Some erosion on downstream side of left abutment
Rock Slope Protection - Riprap Failures	No riprap on slopes
Unusual Movement or Cracking at or near Toe	None observed
Unusual Embankment or Downstream Seepage	Minor seepage through the split stone wall located behind the left training wall
Piping or Boils	None observed
Foundation Drainage Features	None observed
Toe Drains	None observed
Instrumentation System	None observed

INSPECTION CHECK LIST

PROJECT: Pequawket Power Co. Dam, NH

DATE: June 9, 1980

PROJECT FEATURE: Dike Embankment

NAME: _____

DISCIPLINE: _____

NAME: _____

AREA EVALUATED

CONDITIONS

DIKE EMBANKMENT

No Dike

Crest Elevation

Current Pool Elevation

Maximum Impoundment to Date

Surface Cracks

Pavement Condition

Movement or Settlement of Crest

Lateral Movement

Vertical Alignment

Horizontal Alignment

Condition at Abutment and at
Concrete Structures

Indications of Movement of Structural
Items on Slopes

Trespassing on Slopes

Vegetation on Slopes

Sloughing or Erosion of Slopes or Abutments

Rock Slope Protection - Riprap Failures

Unusual Movement or Cracking
at or near Toes

Unusual Embankment or Downstream Seepage

Piping or Boils

Foundation Drainage Features

Toe Drains

Instrumentation System

INSPECTION CHECK LIST

PROJECT: Pequawket Power Co. Dam, NH

DATE: June 9, 1980

PROJECT FEATURE: Intake Channel

NAME: _____

DISCIPLINE: _____

NAME: _____

AREA EVALUATED

CONDITIONS

OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE

No intake structure

a. Approach Channel

Slope Conditions

Bottom Conditions

Rock Slides or Falls

Log Boom

Debris

Condition of Concrete Lining

Drains or Weep Holes

b. Intake Structure

Condition of Concrete

Stop Logs and Slots

INSPECTION CHECK LIST

PROJECT: Pequawket Power Co. Dam, NH

DATE: June 9, 1980

PROJECT FEATURE: Control Tower

NAME: _____

DISCIPLINE: _____

NAME: _____

AREA EVALUATED

CONDITIONS

OUTLET WORKS - CONTROL TOWER

No control tower

a. Concrete and Structural

General Condition

Condition of Joints

Spalling

Visible Reinforcing

Rusting or Staining of Concrete

Any Seepage or Efflorescence

Joint Alignment

Unusual Seepage or Leaks in
Gate Chamber

Cracks

Rusting or Corrosion of Steel

b. Mechanical and Electrical

Air Vents

Float Wells

Crane Hoist

Elevator

Hydraulic System

Service Gates

Emergency Gates

Lightning Protection System

Emergency Power System

Wiring and Lighting System

INSPECTION CHECK LIST

PROJECT: Pequawket Power Co. Dam, NH

DATE: June 9, 1980

PROJECT FEATURE: Transition and Conduit

NAME: _____

DISCIPLINE: _____

NAME: _____

AREA EVALUATED

CONDITIONS

OUTLET WORKS - TRANSITION AND CONDUIT

No transition or conduit

General Condition of Concrete

Rust or Staining on Concrete

Spalling

Erosion or Cavitation

Cracking

Alignment of Monoliths

Alignment of Joints

Numbering of Monoliths

INSPECTION CHECK LIST

PROJECT: Pequawket Power Co. Dam, NH

DATE: June 9, 1980

PROJECT FEATURE: Outlet Structure

NAME: _____

DISCIPLINE: _____

NAME: _____

AREA EVALUATED

CONDITIONS

OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL

No outlet structure

General Condition of Concrete

Rust or Staining

Spalling

Erosion or Cavitation

Visible Reinforcing

Any Seepage or Efflorescence

Condition at Joints

Drain holes

Channel

Loose Rock or Trees Overhanging
Channel

Condition of Discharge Channel

INSPECTION CHECK LIST

PROJECT: Pequawket Power Co. Dam, NH

DATE: June 9, 1980

PROJECT FEATURE: Spillway Weir

NAME: _____

DISCIPLINE: _____

NAME: _____

AREA EVALUATED

CONDITIONS

OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS

a. Approach Channel

General Condition

Good

Loose Rock Overhanging Channel

None

Trees Overhanging Channel

None

Floor of Approach Channel

Not visible beneath water surface

b. Weir and Training Walls

General Condition of Concrete

Good

Rust or Staining

None

Spalling

Some erosion of both training walls at downstream toe

Any Visible Reinforcing

None

Any Seepage or Efflorescence

None visible

Drain Holes

None observed

c. Discharge Channel

General Condition

Fair

Loose Rock Overhanging Channel

None

Trees Overhanging Channel

Trees overhanging discharge channel

Floor of Channel

Boulders and cobbles

Other Obstructions

Five logs lying on spillway discharge apron

Other Comments

INSPECTION CHECK LIST

PROJECT: Pequawket Power Co., Dam, NH DATE: June 9, 1980

PROJECT FEATURE: Outlet Works - Service Bridge NAME: _____

DISCIPLINE: _____ NAME: _____

AREA EVALUATED	CONDITIONS
<u>OUTLET WORKS - SERVICE BRIDGE</u>	
a. Super Structure	
Bearings	Service bridge is concrete slab above stoplog bays
Anchor Bolts	Not applicable. Service bridge integrally poured with training walls.
Bridge Seat	None
Longitudinal Members	Not applicable - see bearings
Under Side of Deck	Not applicable, slab is reinforced concrete
Secondary Bracing	Concrete - good condition
Deck	None
Drainage System	Concrete - one longitudinal hairline crack in top surface of left span
Railings	None
Expansion Joints	Downstream side only
Paint	One over center pier
	Railing in good condition, stanchion beams could use some paint
b. Abutment & Piers	
General Condition of Concrete	Good
Alignment of Abutment :	Good
Approach to Bridge	Good
Condition of Seat & Backwall	Good

APPENDIX B
ENGINEERING DATA

AVAILABLE ENGINEERING DATA

A set of plans dated 1969 by the New Hampshire Water Resources Board, showing plan, elevation, and section for reconstruction of the dam were obtained from the New Hampshire Water Resources Board, Concord, New Hampshire. A copy of the dam's operational log was also obtained from the state of New Hampshire Water Resources Board. No in-depth engineering calculations, as-built drawings, or specifications were found.

PAST INSPECTION REPORTS

DATE May 9, 1969
FROM Francis C. Moore
SUBJECT Pequawket Pond Dam
TO Vernon A. Knowlton

On May 6, 1969, I visited Pequawket Pond dam in the center of Conway Village. The top part of the wood spillway on the left of the sluiceway is badly disintegrated. There is some disintegration of the level section to the right of the sluiceway (12' long - 2 1/2' wide) but it does not affect level of the pond. Also, the right side does not leak appreciably as it has earth and stone fill against it.

The break on the left is between 9 and 11 feet wide and tapers down to 3' near the lower end of the sluiceway. Two A frames holding the wood facing on the left of sluiceway has disappeared or moved several feet out of line at the top of spillway. The third A-frame is not secure at the top and the downstream vertical post tips several inches downstream.

To temporarily seal the spillway, a timber 14' to 16' long across the top of spillway near the sloping face could be secured to the spillway. Vertical planking (2 layers) with joints overlapped could extend down from this heavy timber to cover the hole.

This spillway should be replaced with a concrete or stop log type spillway at the earliest possible date.

Suggested material list:

16' - 6" x 12" timber for top wholer
240 bf of 2" x 8" or 2" x 10" planking - 12'± long.

FCM/jb

July 12, 1967

Mr. John Hutchins
Albany
New Hampshire

Dear Mr. Hutchins:

In response to your letter regarding leakage at the outlet dam to Pequawket Pond, the Water Resources Board Operator of Dams investigated the situation on July 11, 1967.

He found that one of the lower ~~wooden stoplogs~~ had evidently rotted and was causing most of the leakage. A new plank was placed in the rotted area to stop the loss of water. When the water is lowered in the fall, the Board will inspect the structure to determine what repairs are needed to maintain the dam.

Thank you for informing the Water Resources Board of this problem. If you have further questions or information on this dam, feel free to contact us any time.

Very truly yours,

Robert W. Livingston
Civil Engineer

rw1:c

Final Report on Unauthorized Operation of the Pequawket Dam in
Conway, N. H.


Friday, June 9, 1961

Arriving at the State-owned dam on Pequawket Pond, Conway, N. H., I found that new stop logs had been placed on the dam closing the opening completely. The pond water level was 8" below the spillway crest.

I contacted Mr. Hale on the status of the repairs to the water line under the pond and he informed me that the repair work has been abandoned and a new by-pass line was being installed - eliminating the need of lowering the pond further.


Vernon A. Knowlton
Civil Engineer

MAIN STREET BRIDGE — EAST
TOWARD VILLAGE



PEQUAWKET DAM, Conway, N. H.

Water surface at rear of Kennett's was 0.45' lower on 6/23/60.

Water surface now is 90.04' at Kennett's. Elevation desired at Cotton's is 1.90' higher than present water surface- or 91.94' elevation; 1.45' higher than on Monday, June 20, 1960.

Dam width is 40.5 feet with west abutment flaring out somewhat and straight on east abutment.

Assuming 27.4 square mile drainage area and 0.3 cfs/sq. mi. runoff, 8.2 cfs or greater would occur on the average all but possibly 7 days a year. The leakage in the dam is at least this amount and probably cannot be easily reduced much. From this information, the spillway should be cut about 1'-1½" as shown on accompanying plan.

NOTES ON DAM:

Dam has eight bents between 9 A-frames in 22.0 feet on the east end of the dam to the 4.7' wide sluiceway. From the sluiceway opening to the west abutment, there are five bents between 6 A-frames in 13.8 feet. One foot of water on spillway is 135 cubic feet per second or 5 cfs/sq. mi.

At the sluiceway 9" beyond line of other posts, two posts are side by side in line with other posts. On the west end of sluiceway, there are two 6"x9" posts with the downstream posts set 9" beyond line of other posts. Also a 2"x8" is scabbed to the rear post.

At third points of east section of spillway, and next to sluiceway, three one inch steel rods run diagonally and parrallel to upstream face of dam through the horizontal whaler on top of posts. There are also two steel rods on the west side of the sluiceway, one near sluiceway and one at mid point.

The sluiceway is side-planked with double 2" planks at top 2 or 3 feet with only single planking below. There is a 3" wide opening in planking on the west side above the mid point.

The third vertical post from the sluiceway going west has leaned downstream 4".

There is some leakage through the planking but not really serious. At times of draught, the sluiceway should be completely shut off.

Top ends of diagonal timbers that are planked are partially rotted off to the whalers on the vertical posts. Some diagonals are transferring no load to top of vertical posts. The planking, braces, whalers, vertical posts are sound. The top horizontal flooring is gone on the east end and partially gone on the west end.

Conway, New Hampshire
September 2, 1952

Mr. Walter G. White, Chairman
Water Resources Board, State of N. H.
Ossipee, New Hampshire

Dear Mr. White:


In accordance with your letter of August 29, 1952, and our telephone conversation this morning, enclosed please find application blank for repair of a dam at Conway.

As I told you, this work has been done. All the old uprights in the dam were removed and replaced by 8x10 hemlocks. The old planks from the top to within five feet of the bottom of the dam were removed and replaced by 2x10 hemlock planks laid double.

If you need any further information, please advise.

Very truly yours,

The Pequawket Power Company


Treas.

Form WCC. 1
7/30/37

THE STATE OF NEW HAMPSHIRE

County of Carroll, ss. September 2 19 52

PETITION FOR APPROVAL OF THE CONSTRUCTION OR

REPAIR OF DAM AT Conway, New Hampshire

TO THE WATER CONTROL COMMISSION:

In compliance with the provisions of Laws of 1937, c. 133, an Act establishing a Water Control Commission,

We, the Pequawket Power Company, of Conway, N.H. a partnership
I, (Here state name of person or persons, partnership, association, corporation,
etc.)

hereby petition the Water Control Commission ~~for approval to construct, to recon-~~
~~struct~~, to make repairs to, a dam along, or (cross out portion not applicable)
across Pequawket Pond
(Here state name of stream or body of water)

at a point in Conway Village on Route 16 in the Town of Conway, N.H.
(Here give location, by distance from mouth of stream, county

or municipal boundary)

in the town (s) of _____

in accordance with PRELIMINARY PLANS, and SPECIFICATIONS FILED WITH THIS APPLICA-
TION and made a part hereof.

Form WCC. 1-p. 2
7/30/37

The purpose of the proposed construction is to make necessary repairs
(Here briefly state use to
to dam
which stored water is to be put)

The construction will consist of putting in necessary new braces and
(Here give brief description of work con-
supporting timbers and boards on dam, to maintain its use
templated including height of dam)

All land to be flowed ^{is not}
_{is} owned by applicant.

Pequawket Power Company

Edward W. Wabbe Treas.

Address Conway, N. H.

Note: This application together with plans, specifications and information and data filed in connection herewith will remain on file in the office of the Water Control Commission.

June 28, 1946

Case 52.02

Pequawkett Pond Outlet, Conway, N. H.

The condition of this dam is fair. Some recent repairs have been made to the abutments. The timber "A" frame dam will require some new planking within a few years, - but not necessary to be done immediately.

Leonard R. Frost
Engineer

NEW HAMPSHIRE
WATER RESOURCES
BOARD
CONCORD, N. H.

PROJECT

FILE

SUBJECT

ACC

COMPUTER




CHECKER

CONT.
FROM ACC.

CONT.
ON ACC.

SUMMARY
ON ACC.

DATE



NEW HAMPSHIRE WATER CONTROL COMMISSION DATA ON DAMS IN NEW HAMPSHIRE

LOCATION

STATE NO.

Town: County
Stream
Basin-Primary: Secondary
Local Name
Coordinates—Lat.: Long.

GENERAL DATA

Drainage area: Controlled Sq. Mi.: Uncontrolled Sq. Mi.: Total ^{Feb. 14} 27.4 Sq. Mi.
Overall length of dam ft.: Date of Construction
Height: Stream bed to highest elev. ft.: Max. Structure 111.5' - 112.0' ✓ ft.
Cost—Dam: Reservoir

DESCRIPTION

111.5' - 112.0' 11" 11" 11"

Waste Gates

Type
Number: Size ft. high x ft. wide
Elevation Invert: Total Area sq. ft.
Hoist

Waste Gates Conduit

Number: Materials
Size ft.: Length ft.: Area sq. ft.

Embankment

Type
Height—Max. ft.: Min. ft.
Top—Width: Elev. ft.
Slopes—Upstream on: Downstream on
Length—Right of Spillway: Left of Spillway

Spillway

Materials of Construction
Length—Total ft.: Net ft.
Height of permanent section—max. 111.5' - 112.0' ft.: Min. 111.5' - 112.0' ft.
Flashboards—Type None: Height ft.
Elevation—Permanent Crest: Top of Flashboard
Flood Capacity 1000 cfs.: cfs/sq. mi.

Abutments

Materials:
Freeboard: Max. 111.5' - 112.0' ft.: Min. 111.5' - 112.0' ft.

Headworks to Power Devel.—(See "Data on Power Development")

OWNER: Date 11/1/54

REMARKS

111.5' - 112.0' 11" 11" 11"

NEW HAMPSHIRE WATER CONTROL COMMISSION DATA ON RESERVOIRS & PONDS IN NEW HAMPSHIRE

LOCATION

AT DAM NO. 5202

Town Conway: County Saco

Stream Panama Road Outlet

Basin—Primary Saco R: Secondary Saco R

Local Name

DRAINAGE AREA

Controlled Sq. Mi.: Uncontrolled Sq. Mi.: Total Sq. Mi.

ELEVATION vs. WATER SURFACE AREA vs. VOLUME

Point	Head Feet	Surface Area Acres	Volume Acre Ft.
(1) Max. Flood Height
(2) Top of Flashboards
(3) Permanent Crest
(4) Normal Drawdown	<u>146</u>
(5) Max. Drawdown
(6) Original Pond	<u>U.S.G.S. 465</u>

Base Used: Coef. to change to U.S.G.S. Base

RESERVOIR CAPACITY

	Total Volume	Useable Volume
Drawdownft.ft.
Volumeac. ft.ac. ft.
Acre ft. per sq. mi.
Inches per sq. mi.

USE OF WATER Domestic- Recreation

OWNER Pemquett Power Co Conway N.H.

REMARKS

Tabulation By A. N. A. P. T. Date Nov 14, 1933

PUBLIC SERVICE COMMISSION OF NEW HAMPSHIRE—DAM RECORD

I-5241

TOWN	CONWAY	TOWN NO.	2	STATE NO.	52.12
RIVER STREAM	Pequawket Pond Outlet				
DRAINAGE AREA	POND AREA 123				
DAM TYPE	"A" Frame	FOUNDATION NATURE OF Earth			
MATERIALS OF CONSTRUCTION	Riber, Split Stone				
PURPOSE OF DAM	POWER—CONSERVATION—DOMESTIC—RECREATION—TRANSPORTATION—PUBLIC UTILITY				
HEIGHTS, TOP OF DAM TO BED OF STREAM	14'	TOP OF DAM TO SPILLWAY CRESTS 3'-7" - 4'-5"			
SPILLWAYS, LENGTHS DEPTHS BELOW TOP OF DAM	40' Approx.	LENGTH OF DAM Approx. 120'			
FLASHBOARDS TYPE, HEIGHT ABOVE CREST	None				
OPERATING HEAD CREST TO N. T. W.	TOP OF FLASHBOARDS TO N. T. W.				
WHEELS, NUMBER KINDS & H. P.					
GENERATORS, NUMBER KINDS & K. W.					
H. P. 90 P. C. TIME 100 P. C. EFF.	H. P. 75 P. C. TIME 100 P. C. EFF.				
REFERENCES, CASES, PLANS, INSPECTIONS					
REMARKS					

OWNER - Pequawket Power Company

CONDITION - Fair

LENAE - Yes. Will be subject to periodic inspection.

To the Public Service Commission:

The foregoing memorandum on the above dam is submitted covering inspection made July 14, 1936, according to notification to owner dated June 29, 1936, and bill for same is enclosed.

D. Waldo White
Chief Engineer

July 23, 1936
Copy to Owner

INVENTORY OF DAMS AND WATER POWER DEVELOPMENTS

BASIN	<u>Jack</u>	NO.	<u>2</u>	<u>I-5241</u>
RIVER	<u>Pequawket Pond Outlet</u>	MILES FROM MOUTH	<u> </u>	<u>D.A.SQ.MI.</u>
TOWN	<u>Canterbury</u>	OWNER	<u>Pequawket Pond Co.</u>	
LOCAL NAME	<u>CP DAM</u>			
BUILT		DESCRIPTION	<u>4" Frame — Timber Split Stone</u>	
			<u>ON EARTH</u>	

POND AREA-ACRES	<u>142.84</u>	DRAUGHTON FT.	POND CAPACITY-ACRE FT.
HEIGHT-FOOT TO BED OF STREAM-FT.	<u>14</u>	MAX.	MIN.
OVERALL LENGTH OF DAM-FT.	<u>120 ±</u>	MAX. FLOOD HEIGHT ABOVE CREST-FT.	
PERMANENT CREST ELEV. U.S.G.S.		LOCAL GAGE	
TAILWATER ELEV. U.S.G.S.		LOCAL GAGE	
SPILLWAY LENGTHS-FT.	<u>40 ±</u>	FREEBOARD-FT.	<u>3.172</u>
FLASHBOARDS-TYPE, HEIGHT ABOVE CREST	<u>11.00 ±</u>		
WASTE GATES-NO.		WIDTH MAX. OPENING	DEPTH STILL BELOW CREST

REMARKS Credit to FRU

7F John B. Hawckett Bk, Sacramento

[illegible]

USE Domestic Recreation

REMARKS Menage

DATE 7/14/36

OPERATIONAL LOG

PEQUAKET POND DAM

FULL LAKE 7.00 FT. MEASURED ON UPSTREAM SIDE OF
MIDDLE PIER.

2 Logs Per Bay. 6 Bays across = 12 Logs Total.
Stops 4' x 7' x 5' 11"

PEQUAWKET POND DAM DATA

Dam purchased on May 4, 1961 for \$1.00 by the New Hampshire Water Resources Board. No major repairs needed as the crest had been rebuilt by the previous owners.

Upstream storage at Davis Pond - 28 Acres
Upper Pequawket Pond - 14 Acres
Little Pea Porridge Pond - 4 Acres
Middle Pea Porridge Pond - 43 Acres
Pea Porridge Pond - 144 Acres
All natural storage ponds - (total 231 acres)

Pequawket Pond Area = 143 acres
" " drainage area = 27.4 sq. miles
Total drawdown = 6.79' +
Spillway length = 40.5'
Stoplog width = 4.7'
Freeboard = 5.5'
Total estimated storage to full pond = 550 acre feet

15 year frequency flood = 1,060 cfs
100 " " = 2,590 cfs

Spillway capacity = 1,730 cfs

1" from total drainage area raises pond 48 inches (assuming upstream storage holds its share)

Flow over spillway (stoplogs in)

6"	-	47 cfs
12"	-	133 cfs
18"	-	245 cfs
24"	-	376 cfs
36"	-	692 cfs
48"	-	1064 cfs

Increases by Sluiceway discharges

Depth of stoplogs out at no flow over spillway

12"	-	16 cfs
24"	-	45 cfs
36"	-	82 cfs

Depth of stoplogs out at 12" flow over spillway

12"	-	39 cfs
24"	-	68 cfs
36"	-	95 cfs

Boards = 2" x 8" x 6"
(stream cut)

NEW HANDSHING
WATER RESOURCES
BOARD
CONCORD N.H.

PROJECT
SUBJECT

COMPUTOR

CHECKER

CONT.
FROM ACC.

CONT.
ON ACC.

SUMMARY
ON ACC.

DATE

11/3/61- Pulled 5 stoplogs. Water 3" over Spillway. 14K
lost three boards downstream (2 on bank)
12-62 Water 8 1/2" over Spillway. Too much flow
to put in boards. 14K
5-24-62 Put in 5 boards. Water 12" over spillway.
14K
11-20-62 Water 14" over spillway. Pulled 4 stoplogs. 14K
Water even with crest of Spillway. Pulled
one Board (5 out) 14K
5-17-62 Put in 5 boards - 2 out that were
removed by unauthorized personnel.
Water approx. 14" below spillway
& spilling enough for fish flowage. Talked
with M. Lovelace of Conway Ins. Agency,
about his field being unable to drain. 14K
6-4-63 Put in 3 1/2 Boards to bring opening up to crest
of spillway. Water 2" over spillway. Cleared
debris off dam. 14K
8-3-63 Water just over spillway. Checked complaint
on closing off stream in cemetery by the town.
7-4-63 Water just over spillway. 14K
10-24-63 * Pulled 6 boards - Water 1/4" over spillway
prior to removal. 14K
3-4-64 Water 1' below spillway. Approx. 4' through
board section. 14K
5-6-64 Pulled large log out of stoplog section &
put in 4 boards - (4 out) Water 6" below
spillway crest. Cleared other debris from
area. 14K
5-20-64 Pulled log from stoplog section & cleaned debris
from spillway. Water 5" over spillway. Could
not put in last 4 boards yet. 14K

PROJECT: **Pequawket Pond**

FILE _____
ACC. _____

COMPUTER _____

CHECKER _____

CONT.
FROM ACC. _____

CONT.
ON ACC. _____

SUMMARY
ON ACC. _____

DATE _____

Date

Spillway

Notes

Name

6-1-64	Put in 4 boards - Water 3" below spillway.	MEK
7-6-64	Mr. Frost checked dam - O.K.	MEK
8-31-64	Water just over spillway - O.K.	VAK
8-26-64	Water 1.5" over spillway	VAK
11-6-64	Water even with top of spillway - Pulled 6 boards	MEK
1-22-65	Water approx. 2' below top of spillway - no obstructions	MEK
5-7-65	Put in 6 boards - Cleaned logs and debris out of stoplog section. Water drizzling over spillway.	MEK
10-20-65	"Buz" Coleman called & requested early draw down for shore work. Pulled 6 boards - 2 or 3 left - 1" over crest.	MEK
5-19-66	1 1/2 feet below crest. Put in 10 boards - dam free of debris.	MEK
Labor Day	- Pond was drawn down at request of town to lay water line & then refilled - memo.	
11-1-66	+ 2" over crest. pulled 7 boards & cleaned debris off dam.	MEK
5-31-67	Water flowing thru spillway	MEK
6-8-67	PUT IN 7 BOARDS WATER \pm 18" BELOW SPILL	MEK
7-11-67	2 ND BOARD FROM BOTTOM BROKEN REPLACED (SOME LEAKAGE) 15 CFS	MEK
8-2-67	EVEN WITH SPILL	MEK
8-14-67	Replaced top two stop logs one 7" - one 4" ^{1/2} "	MEK
11-1-67	PULLED OUT THE 6 BOARDS O.K. FOR WINTER - 48" TO BOARD	MEK
2-14-68	Water flowing thru spillway	MEK
4-9-68	3 RD stoplog area tonight put in logs	MEK
5-7-	- 2.0 BELOW SPILL ALL BOARDS BUT COULD NOT PUT IN BOTTOM STOP	MEK
5-15-	- 2.4 " " PUT IN ALL BOARDS (12) 6 UNDER WATER 6 OUT OF WATER	MEK
7-7-67	4" \pm over spillway (to crest) - stop on spillway	MEK
9-12-68	Replaced 3 stoplogs -	MEK
10-4-68	- 1.25' Below Spillway all stoplogs in	MEK
11-7-68	+ 0.20' over spillway. Pulled 4 stoplogs	MEK
12-13-68	- 0.7 PUT IN IRON POST FOR FENCE FENCE NOW FIXED	MEK
4-23-69	+ 1 or more PULLED OUT 1 STOP NOW 6 OUT SET FOR WINTER	MEK
5-6-69	- 0.7 Top planks each side of stoplog section out. About 2' down on right for 10' & down on left for 2'	MEK
12-1-69	Checked condition of dam & made report of damage.	MEK
	Stoplog ^{B-22} - 22' long	MEK
	Pulled down 22' from crest - 11' + 11'	MEK

NEW HAMPSHIRE PROJECT
WATER RESOURCES SUBJECT
BOARD
CONCORD, N. H.

Pegquawket Lake

94055 Darp

FILE

6 BAYS

ACC.

CENTER

2

17.0 BELIN CENTER PIER FULL LAN.

COMPLETED

PIER

CHECKER

CONT. FROM ACC

CONT. ON ACC

SUMMARY ON ACC

DATE

5-8-70	23"	PUT IN 47 Logs. Notched ends + Tightened Screw Eyes. LTR	
4-1-70	5" +	LARGE QUANTITY OF DEBRIS RESTRICTING FLOW REMOVED. D.M.V.	
		47 LOGS FROM CTR. BAYS & MOST OF DEBRIS EXCEPT FOR 3 LARGE LOGS ON THE UPSTREAM SIDE & 1 LOG ON TOP OF STOPLOG 13 BAY LEFT NOTE TO MRS. BRITCHE CRANFORD DRIVE THAT POND WILL REcede.	
5-5	-7.5 IN	PULLED OUT 2 STOPS IN TOP ROW, PUT IN 15 SAND BAGS TO STOP LEAK	MC
8-14	-6.11 IN		MC
9-2-70	-6.75	Levelled Stop Log house. Installed Locking Devices LTR	
		Removed Large Log From 2 nd Bay	LSN
9-4-70	-	5" over 2 bags	5(17)
10-5-70	-6.68	Took out 3 Logs From 2 Bay (making 4 Logs out of This Bay)	LSN
10-7-70	-7.35	Took out 3 Logs From 2 Bay (making 7 Logs out)	LSN
11-7-70	-8.3	4 bays have stops 26" out of water, 1 with 18 1/2" out of water. 25" in water	5(17)
3-25-71	-8.9	Pulled Last Bay Down To one Log	LSN
4-30-71	-7.1	Removed 2 Logs From bays. 2 Large Logs caught in dam	LSN
5-25-71	-9.3	Level is -2.7' below full pond. All stops in - Minor leakage	LSN
6-6-71	-8.0	1.3' L	LSN
June 8, 71		+0.1 over Stop Logs (Lots of TRASH)	LSN
7/7/71	-7.9	+0.2 " " " Center stops in both bays out. There are many logs in front of center section, including trees, debris, etc. Level 0.3' below full pond	LSN
7/16/71		even w/ stops except center bays, only 1 log out each bay in sight	LSN
7/16		2 stop logs have no locking device, North on North side of dam	LSN
8/16	-6.7	PULLED OUT (2) STOPS (4) OUT IN BOX CUT BRUSH	MC
9-23	-6.7	- .75 BELOW 3 BAYS (4) OUT OVER 3 BAYS	MC
11-1	-6.6	CLEANED DEBRIS PULLED (4) OUT IN 2 BAYS (1) OUT IN 2 BAYS (10) IN BOX	MC
11-10	-9.7	" (7) " " " 2 BAYS HAVE 2 IN	MC
11-11	-9.7	- 3.7 FT. BELOW FULL POND 1 OUT IN 2 BAYS 4 OUT IN 1 BAY 32 IN BOX	D.M.V.
1-6-72	-10.1	PULLED (6) 2 BAY HAVE 1 IN 4 IN IN 1 BAY	MC
2-25	+0.05	OR LOGS IN 2 BAYS COFFER DAM HAS SHALLOW (5 FT) OPENING	MC
3-10-72	-10.5	Audley To Be all out of Lake By 3-10-72	LSN
5-26		PUT IN ALL LOGS (FOR COLEMAN)	MC
5-31	-6.75	PULLED 9 LOGS IN 3 BAYS	MC
8-2-72	-7.0	PUT IN 9 LOGS (ALL IN) Removed 1 Large + 1 Small Logs From Bay area (Trash Logs)	LSN
6-14-72	-6.55	+0.5 OVER 3 BAYS	LSN

REF ID: A64574

- 7 -

5

7-21 7-70 CLEARED OUT ALL BERRIES (11 LOGS 14 BERRIES) *ms*

7-31-72 - 66. 21.15 (See Summary Downstream (1430' E. of 1st))
50.00 (m)

11-2-75-6.5 Pooled 2 Logs from 2nd Bay. 4 Logs of 4th Bay from
Log caught in 2nd Bay - from 2nd Bay 2 Logs
from 3rd Bay area. L31

11-6 PULLER LIPS 1 3/4 HAS 1 1/2 IN NO-NES HAS 1 OUT MC

11-3 TOW BAYS HAVE 12 IN ONE 3 HAS 614 OTHER 84 MC

12-92-99 OK LJN

1-4:3-9.25 OK L5m

1-7-10-10-9-2-2-6

A.H.

1-2 3-2.6 2.1

2-1-99 2-

2-1-1	2.5	0.1	450
-------	-----	-----	-----

5-13-87 Cleared 2 small logs that were in line road.

-8.4

James Henry Smith & George Corbridge

6-1-73 = 645 EIT = 3 loops All loops in New Circuit 2nd time

These names are all from

7-1-73 = 485

1. NAME _____
 2. DATE _____
 3. TOPIC _____

REITER was in service from dropped his

1-2	1-5	1-6	1-7	1-8	1-9	1-10	1-11	1-12	1-13	1-14	1-15	1-16	1-17	1-18	1-19	1-20	1-21	1-22	1-23	1-24	1-25	1-26	1-27	1-28	1-29	1-30	1-31	1-32	1-33	1-34	1-35	1-36	1-37	1-38	1-39	1-40	1-41	1-42	1-43	1-44	1-45	1-46	1-47	1-48	1-49	1-50	1-51	1-52	1-53	1-54	1-55	1-56	1-57	1-58	1-59	1-60	1-61	1-62	1-63	1-64	1-65	1-66	1-67	1-68	1-69	1-70	1-71	1-72	1-73	1-74	1-75	1-76	1-77	1-78	1-79	1-80	1-81	1-82	1-83	1-84	1-85	1-86	1-87	1-88	1-89	1-90	1-91	1-92	1-93	1-94	1-95	1-96	1-97	1-98	1-99	1-100	1-101	1-102	1-103	1-104	1-105	1-106	1-107	1-108	1-109	1-110	1-111	1-112	1-113	1-114	1-115	1-116	1-117	1-118	1-119	1-120	1-121	1-122	1-123	1-124	1-125	1-126	1-127	1-128	1-129	1-130	1-131	1-132	1-133	1-134	1-135	1-136	1-137	1-138	1-139	1-140	1-141	1-142	1-143	1-144	1-145	1-146	1-147	1-148	1-149	1-150	1-151	1-152	1-153	1-154	1-155	1-156	1-157	1-158	1-159	1-160	1-161	1-162	1-163	1-164	1-165	1-166	1-167	1-168	1-169	1-170	1-171	1-172	1-173	1-174	1-175	1-176	1-177	1-178	1-179	1-180	1-181	1-182	1-183	1-184	1-185	1-186	1-187	1-188	1-189	1-190	1-191	1-192	1-193	1-194	1-195	1-196	1-197	1-198	1-199	1-200	1-201	1-202	1-203	1-204	1-205	1-206	1-207	1-208	1-209	1-210	1-211	1-212	1-213	1-214	1-215	1-216	1-217	1-218	1-219	1-220	1-221	1-222	1-223	1-224	1-225	1-226	1-227	1-228	1-229	1-230	1-231	1-232	1-233	1-234	1-235	1-236	1-237	1-238	1-239	1-240	1-241	1-242	1-243	1-244	1-245	1-246	1-247	1-248	1-249	1-250	1-251	1-252	1-253	1-254	1-255	1-256	1-257	1-258	1-259	1-260	1-261	1-262	1-263	1-264	1-265	1-266	1-267	1-268	1-269	1-270	1-271	1-272	1-273	1-274	1-275	1-276	1-277	1-278	1-279	1-280	1-281	1-282	1-283	1-284	1-285	1-286	1-287	1-288	1-289	1-290	1-291	1-292	1-293	1-294	1-295	1-296	1-297	1-298	1-299	1-300	1-301	1-302	1-303	1-304	1-305	1-306	1-307	1-308	1-309	1-310	1-311	1-312	1-313	1-314	1-315	1-316	1-317	1-318	1-319	1-320	1-321	1-322	1-323	1-324	1-325	1-326	1-327	1-328	1-329	1-330	1-331	1-332	1-333	1-334	1-335	1-336	1-337	1-338	1-339	1-340	1-341	1-342	1-343	1-344	1-345	1-346	1-347	1-348	1-349	1-350	1-351	1-352	1-353	1-354	1-355	1-356	1-357	1-358	1-359	1-360	1-361	1-362	1-363	1-364	1-365	1-366	1-367	1-368	1-369	1-370	1-371	1-372	1-373	1-374	1-375	1-376	1-377	1-378	1-379	1-380	1-381	1-382	1-383	1-384
-----	-----	-----	-----	-----	-----	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------

[Faint handwritten notes at the bottom of the page]

1-11-13 - C. G. Large Log in one bay, K&K in helicopter, there is
a large log in one bay, K&K in helicopter, there is

* HARRY FORDONAL CHECK THE FUTURE HISTORY OF THE 1 SECOND SECTION (THE OLDS) 1/2

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100

8-12 = 6.7 clear dots + 0.5 over lgs. on brush

Bx Stop Log Book

8-20 - 6.0 CLEARED DEBRIS - NOW APPROX 424 2259 LX AC

9/2-6.95

9-20-68 Max / Lerr

2.2. 13-1.0

10-013-70 Filled 2 Loss. Cleared 1 Log & much Debris. L4

10-17-73	- 7.5 z. Brays Spiccing	Pot - 1000000
----------	-------------------------	---------------

1-1-67 PULLED 21260 1 IN 5 1/2 1/2

[illegible]

(Signature)

18 - 24 (1918) 44 (1919) 50 (1920) 55 (1921) 60 (1922) 65 (1923) 70 (1924) 75 (1925) 80 (1926) 85 (1927) 90 (1928) 95 (1929) 100 (1930) 105 (1931) 110 (1932) 115 (1933) 120 (1934) 125 (1935) 130 (1936) 135 (1937) 140 (1938) 145 (1939) 150 (1940) 155 (1941) 160 (1942) 165 (1943) 170 (1944) 175 (1945) 180 (1946) 185 (1947) 190 (1948) 195 (1949) 200 (1950) 205 (1951) 210 (1952) 215 (1953) 220 (1954) 225 (1955) 230 (1956) 235 (1957) 240 (1958) 245 (1959) 250 (1960) 255 (1961) 260 (1962) 265 (1963) 270 (1964) 275 (1965) 280 (1966) 285 (1967) 290 (1968) 295 (1969) 300 (1970) 305 (1971) 310 (1972) 315 (1973) 320 (1974) 325 (1975) 330 (1976) 335 (1977) 340 (1978) 345 (1979) 350 (1980) 355 (1981) 360 (1982) 365 (1983) 370 (1984) 375 (1985) 380 (1986) 385 (1987) 390 (1988) 395 (1989) 400 (1990) 405 (1991) 410 (1992) 415 (1993) 420 (1994) 425 (1995) 430 (1996) 435 (1997) 440 (1998) 445 (1999) 450 (2000) 455 (2001) 460 (2002) 465 (2003) 470 (2004) 475 (2005) 480 (2006) 485 (2007) 490 (2008) 495 (2009) 500 (2010) 505 (2011) 510 (2012) 515 (2013) 520 (2014) 525 (2015) 530 (2016) 535 (2017) 540 (2018) 545 (2019) 550 (2020) 555 (2021) 560 (2022) 565 (2023) 570 (2024) 575 (2025) 580 (2026) 585 (2027) 590 (2028) 595 (2029) 600 (2030) 605 (2031) 610 (2032) 615 (2033) 620 (2034) 625 (2035) 630 (2036) 635 (2037) 640 (2038) 645 (2039) 650 (2040) 655 (2041) 660 (2042) 665 (2043) 670 (2044) 675 (2045) 680 (2046) 685 (2047) 690 (2048) 695 (2049) 700 (2050) 705 (2051) 710 (2052) 715 (2053) 720 (2054) 725 (2055) 730 (2056) 735 (2057) 740 (2058) 745 (2059) 750 (2060) 755 (2061) 760 (2062) 765 (2063) 770 (2064) 775 (2065) 780 (2066) 785 (2067) 790 (2068) 795 (2069) 800 (2070) 805 (2071) 810 (2072) 815 (2073) 820 (2074) 825 (2075) 830 (2076) 835 (2077) 840 (2078) 845 (2079) 850 (2080) 855 (2081) 860 (2082) 865 (2083) 870 (2084) 875 (2085) 880 (2086) 885 (2087) 890 (2088) 895 (2089) 900 (2090) 905 (2091) 910 (2092) 915 (2093) 920 (2094) 925 (2095) 930 (2096) 935 (2097) 940 (2098) 945 (2099) 950 (2100) 955 (2101) 960 (2102) 965 (2103) 970 (2104) 975 (2105) 980 (2106) 985 (2107) 990 (2108) 995 (2109) 1000 (2110) 1005 (2111) 1010 (2112) 1015 (2113) 1020 (2114) 1025 (2115) 1030 (2116) 1035 (2117) 1040 (2118) 1045 (2119) 1050 (2120) 1055 (2121) 1060 (2122) 1065 (2123) 1070 (2124) 1075 (2125) 1080 (2126) 1085 (2127) 1090 (2128) 1095 (2129) 1100 (2130) 1105 (2131) 1110 (2132) 1115 (2133) 1120 (2134) 1125 (2135) 1130 (2136) 1135 (2137) 1140 (2138) 1145 (2139) 1150 (2140) 1155 (2141) 1160 (2142) 1165 (2143) 1170 (2144) 1175 (2145) 1180 (2146) 1185 (2147) 1190 (2148) 1195 (2149) 1200 (2150) 1205 (2151) 1210 (2152) 1215 (2153) 1220 (2154) 1225 (2155) 1230 (2156) 1235 (2157) 1240 (2158) 1245 (2159) 1250 (2160) 1255 (2161) 1260 (2162) 1265 (2163) 1270 (2164) 1275 (2165) 1280 (2166) 1285 (2167) 1290 (2168) 1295 (2169) 1300 (2170) 1305 (2171) 1310 (2172) 1315 (2173) 1320 (2174) 1325 (2175) 1330 (2176) 1335 (2177) 1340 (2178) 1345 (2179) 1350 (2180) 1355 (2181) 1360 (2182) 1365 (2183) 1370 (2184) 1375 (2185) 1380 (2186) 1385 (2187) 1390 (2188) 1395 (2189) 1400 (2190) 1405 (2191) 1410 (2192) 1415 (2193) 1420 (2194) 1425 (2195) 1430 (2196) 1435 (2197) 1440 (2198) 1445 (2199) 1450 (2200) 1455 (2201) 1460 (2202) 1465 (2203) 1470 (2204) 1475 (2205) 1480 (2206) 1485 (2207) 1490 (2208) 1495 (2209) 1500 (2210) 1505 (2211) 1510 (2212) 1515 (2213) 1520 (2214) 1525 (2215) 1530 (2216) 1535 (2217) 1540 (2218) 1545 (2219) 1550 (2220) 1555 (2221) 1560 (2222) 1565 (2223) 1570 (2224) 1575 (2225) 1580 (2226) 1585 (2227) 1590 (2228) 1595 (2229) 1600 (2230) 1605 (2231) 1610 (2232) 1615 (2233) 1620 (2234) 1625 (2235) 1630 (2236) 1635 (2237) 1640 (2238) 1645 (2239) 1650 (2240) 1655 (2241) 1660 (2242) 1665 (2243) 1670 (2244) 1675 (2245) 1680 (2246) 1685 (2247) 1690 (2248) 1695 (2249) 1700 (2250) 1705 (2251) 1710 (2252) 1715 (2253) 1720 (2254) 1725 (2255) 1730 (2256) 1735 (2257) 1740 (2258) 1745 (2259) 1750 (2260) 1755 (2261) 1760 (2262) 1765 (2263) 1770 (2264) 1775 (2265) 1780 (2266) 1785 (2267) 1790 (2268) 1795 (2269) 1800 (2270) 1805 (2271) 1810 (2272) 1815 (2273) 1820 (2274) 1825 (2275) 1830 (2276) 1835 (2277) 1840 (2278) 1845 (2279) 1850 (2280) 1855 (2281) 1860 (2282) 1865 (2283) 1870 (2284) 1875 (2285) 1880 (2286) 1885 (2287) 1890 (2288) 1895 (2289) 1900 (2290) 1905 (2291) 1910 (2292) 1915 (2293) 1920 (2294) 1925 (2295) 1930 (2296) 1935 (2297) 1940 (2298) 1945 (2299) 1950 (2300) 1955 (2301) 1960 (2302) 1965 (2303) 1970 (2304) 1975 (2305) 1980 (2306) 1985 (2307) 1990

11

[illegible]

2011/11/24

1. *Journal of the American Medical Association*, 1997; 277: 1039-1043.

REPORT

FILE 82 00
- 2015-01-01
ACC

DATE	CENTER PIER	DESCRIPTION	DATE
4-2-74	-7.0	Cleared Debris (Saw Box - 1000)	LTJ
5-2-74	-8.5	Put in 3 logs each Low Bay (5 tons)	LTJ
5-2-74	-7.5	Put in 4 logs, now we have 2 logs in each 4 Bay	LTJ
5-16-74	-6.5	1 log in 1 Bay; Rail needs paint, hardware roofing & cleats	PM
6-18-74	-6.5	Cleared Large Low Down Stream Trash	LTJ
6-25-74	-7.0	Put in 4 logs (All in Now) Put on locks	LTJ
7-1-74	-6.5	Recovered Log Boxes with Roofing Paper	LTJ
7-1-74	-6.5	Cleared Trash	SCS
7-1-74	-6.5	2' x 4' Box with paint & steel cables	SCS
7-1-74	-7.2		SCS
7-22-74	-6.9	CLEARED DEBRIS	M
8-12-74	-7.0	Cleared Debris from Stop Section	LTJ
10-4-74	-6.8	Pulled 2 logs (1 from each center Bay)	LTJ
10-6-74	-7.1		LTJ
10-14-74	-7.25	CLEARED DEBRIS	LTJ
11-6-74	-7.0	PULLED 8 LOGS 2 EACH CENTER BAYS ALL OTHER BAYS 1 EACH	LTJ
11-24-74	-7.3	Pulled 4 Logs (2 from each Bay) 2 logs left	LTJ
11-24-74	-7.3	2 logs in each Bay 2 locking devices at each	LTJ
11-24-74	-7.65	OK	LTJ
11-24-74	-7.3	OK	LTJ
1/3-75	-9.1	CLEARED DEBRIS (BEANHEADS DEAD WOOD)	M
1/17-75	-9.6		M
1-21-75	-9.2		LTJ
2-3-75	-9.2		LTJ
3-2-75	-9.3		LTJ
5-9-75	-8.3	Put in 6 logs (3 each Low Bay) 1 Row out + 2 out in	LTJ
5-9-75	-8.3	Low Bay	LTJ
5-11-75	-7.55	Put in 3 logs All in Now Cleared Trash	LTJ
6-4-75	-6.5		LTJ
6-4-75	-6.6	Check in side walk needs epoxy coating	PM
6-4-75	-6.6		LTJ
6-4-75	-6.6	33-4" over logs	LTJ
6-25-75	-6.75	+0.05 over all logs. Clear Trash & Logs from	LTJ
6-25-75	-6.75	Stop Section & Railing needs paint	LTJ
9-1-75	-6.75	OK Rail needs painting	LTJ
9-1-75	-6.75	Painted Railing & cut brush & picked up	LTJ
9-3-75	-6.75	6 ft 8 1/2" from Pier	LTJ
10-1-75	-5.95	CLEAR	LTJ
10-1-75	-6.6	Put 4 logs of 2 Bays Steel (11,125 in 2 center Bays)	LTJ
11-1-75	-7.7	Pulled 2 logs from each Bay	LTJ

NEW HAMPSHIRE PROJECT
WATER RESOURCES SUBJECT
BOARD
CONCORD N.H.

Dequaket

- 1.05' full

COMPUTER CHECKER CONT. FROM ACC. CONT. ON ACC. SUMMARY ON ACC. DATE

Date Genter
Pier

By

SCB

LTm

LTm

LTm

GLK

PDK

LTm

PDK

PDK

PDK

P.M.

SCB

ST

IN Middle Days

GLK

PDK

PDK

PDK

PDK

LTm

LTm

LTm

LTm

LTm

LTm

LTm

LTm

LTm

LTm

12-2-76 Pulled 3 Logs Only 1 Log in each Center bay

2-25-76 -9.6 Area OK.

3-25-76 -9.42 2 Logs caught on center

4-7-76 -9.5 Cleared 1 Log at Stop Bay + 1 To Go.

4-15-76 -8.7 INSTALLED 8 STOP LOGS IN ONE BAY (EVEN W/OTHER BAYS)

REMOVED CAUGHT TREE LOG - ALL CLEAR NOW

ONE BAY STILL EMPTY OF STOP LOGS. HURD ON

STORAGE HOUSE BUILT WOSE FROM TOP OF BOX

5-3-76 -8.2 Put in 9 logs.

5-6-76 -7.0 RE-SET LOGS + TAMPED LOGS TO SEAT + SEAL
LEAKS. MID BAY LOG ELEV. IS - 7.0/2 and
bays are 1 Log high.

5-14-76 -6.1

5-18-76 -6.05 1 Log. Log in one Bay & 2 long locks in 2 Bays

5-20-76 -5.8

6-18-76 C. Crew took new S.L. Box up & removed old one & removed by log from S.L. Bay

7-3-76 -6.75

7-6-76 -6.70 Clear STUMP + debris (all logs in, flowing)

IN Middle Days

8-10-76 -6.3 Removed 2 Logs (center part) (ALL EVEN ACCESS BAYS)

9-2-76 -6.3

9-7-76 After O.K. Some debris AT LOGS (small)

9-14-76 -6.7

10-13-76 -6.6 Little debris in log section!

11-1-76 -6.2 Pulled 5 logs.

10-27-76 -6.2

11-12-76 -7.4 Pulled 3 Logs (2 Top strings now out) (2 Logs + To Go

in 2 Deep bays) (Log Caught in Deck)

1-14-76 -8.7

3-4-77 -8.9 Area OK

B-26

4-22-77 -7.8 Clear some debris, Also REPLACE 4-logs

4-27-77 -7.5 Put in 8 Logs (2 logs out) Cleared Street of Pilewood

PEQUAKET

-7.00 is full lake

DATE	Center Per	REMARKS	BY
5-25-77	-6.95	Put in last 2 Logs (ALLEN) Cleared big log at Stop Section	LTm
6-10-77	-7.60	Clear little debris - C.K.	-4.5-
6-29-77	-7.70	" " " " C.K.	-12.5-
7-8-77	-7.90	" " " " "	ABZ
8-5-77	-8.1	" " " " "	PDZ
8-22-77	-6.9	cleared Schich	LTm
10-4-77	-6.1	Pulled 2 Logs	LTm
10-13-77	-6.30	Pull 1-log (3-4 ft) out 10 ft - clear -	ABZ
10-18-77	-5.50	Pull 7-logs 12 cut total - 3 out E.D. Bay	ABZ
10-31-77	-4.5	Pulled 3 Logs 2 out across + 1 left in bottom of each mid bay winter operation	LTm
11-5-77	-4.5	Clear -	ABZ
1-14-78	-7.3	too over	LTm
1-17-78	-8.30	Clear - (WATER (Rovers) INAK - Moderate)	ABZ
4-13-78	7.2	CLEAR	KTS
5-3-78	-7.6	Pull 4 Logs 2 in Bay 2 in E.D. Bay - Clear -	ABZ
5-3-78	-7.6	Put in 12 Logs (2 more logs to go) Cleared Schich	LTm
5-11-78	-6.0	Remove large log + debris C.K. Replace 4-2 2 to go	ABZ
6-12-78	-7.6	cleared 2 Logs + large debris. Still a Telephone pole + 4 Logs To Go	LTm
6-19-78	-6.5	much debris caught in stop section	ABZ
6-29-78	-6.10	Remove much debris (large logs) also clear section to prevent clogging of future debris (also 7-logs)	ABZ
7-1-78	-6.20	+ 6.20 logs Clear debris. Paint RAIL - Post N.T. Sign	ABZ
7-1-78	-6.2	Pull 1 Log - Clear to go	LTm
7-22-78	-7.35	Removed log found much debris from Stop Section	ABZ
7-22-78	-7.4	clear debris at Stop	LTm
7-22-78	-7.5	" " " " "	LTm
7-22-78	-7.4	Pull 3 Logs (Wootton)	ABZ
7-22-78	-7.3	Pull 2 Logs (Wootton)	ABZ
7-22-78	-7.2	Clear debris	ABZ
7-22-78	-7.2	Clear debris	ABZ

REGULAKET

7.00 12.11.11

FILE

ACC.


DATE


REMARKS

BY



DATE	CHG. DISC	REMARKS	BY
3-5-79	-1.0	clear OK	TL
5-2-79	-1.5	discovered logs - Burst from bays 5 & 11 10 logs (South Low bay) 2 logs lost at 2nd. Last FF	TL
5-17-79	-6.65	REPLACE LAST 2-109'S (All-IN)	TL/F
5-17-79	-6.65	175 logs - Removed del	TL/F
6-1-79	-6.4	all logs in and only a small amount del in logs within some log chain in 8/5 only stop...	TL/F
8-18-79	-6.5		TL/F
8-30-79	-6.8	Cleaned garbage and debris from stoplog bays all OK	TL/F
9-11-79	-6.88	Clear - much glass - litter on top.	TL/F
9-27-79	-6.9	LOTER, CORAL REE. ON STAGES AND NEAR SURFACES	TL/F
10-1-79	-6.9	pull 3-logs 18 ft 109 ahead of bay 12	TL/F
10-31-79	-6.9	pull 3-logs PULLED 3 logs (12 logs out of bays) 2 BAYS HAVE 4 LOGS AND 4 BAYS HAVE 1 LOG OUT	TL/F
12-1-79	-6.95	pull 3-logs - 14-15 ft moving at 4 bays, full out	TL/F
12-1-79	-6.95	pull 10 logs (with ball in water) 2 bays 1-20, 2 bays 2 bays, end bays 8-12, 11-12, 10-11, 9-10, 8-9, 7-8, 6-7, 5-6, 4-5, 3-4, 2-3, 1-2	TL/F
3-9-80	-10.0	Put in 10 stops to get (4 logs in 4 low bays)	TL/F
3-28-80	-8.0	REPLACE 8 109'S, 8 to 10 = 8-10/109'S.	TL/F
4-1-80	-7.65	ALSO NOTE, from drain from stage (109) oil leaking	TL/F
4-1-80	-7.65	Put in 4 stop logs. Then logs are full of debris and logs. Logs should be pulled out	TL/F
4-1-80	-6.00	Pull 8-logs Remove large logs from in front.	TL/F
5-1-80	-7.5	REPLACED 17 LOGS - LEFT BAYS UP TO FULL; 2 RIGHT BAYS NEED 1 LOG AND 1 BAY NEED 2 LOGS. 4 LOGS NEED TO BE MADE LENGTHS 5'-10" HOWEVER, IF -6.5 IS FULL POND, THEN THERE ARE TWO EXTRA LOGS THE LEFT BAYS NEED TO BE LOADED BY 1 STOP AND ONE STOP ON NEEDS 1 LOG, THEREFORE, THE TWO EXTRA LOGS REPLACE LOGS, FULL 2 EX LOGS. - ALL-IN. Rem-d.	TL/F

PLANS AND DETAILS







ELEVATION LAST ARGUMENT
1000 1/2 "10"




TYPICAL STANCHION BEAM
Scale: 1/8" = 1'-0"


Designed by J. K. CALDWELL
 Drawn by J. M. CALDWELL
 Traced by _____
 Checked by R. L. Lenz




STOPL-LOCKING DEVICE
Scale 1"=1'-0"




112. CAPITAL / A.T. DETAIL
10' 1" x 3"




Typical Topics to Write:
1. Myself



SUMMARY - 10/15/54



Ex. 5 of STANCHION TEAM
Scale: 1/4" = 1'-0"



7075-10-0

The lower end of the pipe must be cut at the right angle which means that the lower end of the lower stem things will be on the same plane as the bottom of the angle. The place where the lower stem is cut is the remaining horizontal leg in the lower end of the pipe. Work for the horizontal leg.

2 miles E. of
7 miles S. of

- 4 K... ..
1000, 1010, 1020

STATION BEAM
12 1/2" x 1-0"


ONLY A NEW -

REINFORCING STEEL 30

NEW HAMPSHIRE WAT.
- CONCO.

Heat scale:
As Voted


242




1/2" x 1/2" x 1/2" E

5' x 5' x 10' R

HORIZONTAL JOINT DETAIL
Scale 1" = 3'




TYPICAL DETAILING DETAIL
Scale 1" = 3'



SIDEWALK JOINT DETAIL
Scale 1" = 2'

Weld

Temporary steel reinforcement



TEMPORARY STEEL REINFORCEMENT
Scale 1" = 1'-0"

5202

Notes: 1. All dimensions are to center of reinforcement bars. 2. The reinforcement bars shall be placed in the concrete at the time of pouring. 3. The reinforcement bars shall be placed in the concrete at the time of pouring. 4. The reinforcement bars shall be placed in the concrete at the time of pouring.

ALSO HORN POND DAM
REGULAWKET POND DAM

CONWAY, NEW HAMPSHIRE

REINFORCING STEEL & DETAILS

NEW HAMPSHIRE WATER RESOURCES BOARD
- CONCORD, N. H. -

Sheet scale:
As Noted

Sheet 3 of 3

Oct 1969

A hand-drawn floor plan of a three-story building, oriented with the entrance at the bottom. The plan is divided into three main vertical sections by two interior walls. The leftmost section is labeled '11.04 P37 (Top Wall)' at the top and '11.04 P34 (Top Wall)' on the left side. The middle section is labeled '5.04 P38 (Top Wall)' and '5.04 P33 (Top Wall)' at the top, and '11.04 P34 (Top Wall)' and '11.04 P36 (Top Wall)' on the left side. The rightmost section is labeled '8.04 P37 (Top Wall)' at the top and '13.04 P35 (Top Wall)' on the right side. The bottom of the plan is labeled '4.04 DOWN' with an arrow pointing downwards. The plan includes various dimensions and room labels, such as '11.04 P37 (Top Wall)', '5.04 P38 (Top Wall)', '8.04 P37 (Top Wall)', '11.04 P34 (Top Wall)', '5.04 P33 (Top Wall)', '11.04 P36 (Top Wall)', '13.04 P35 (Top Wall)', and '4.04 DOWN'.

SIDEWALL


#4P34

#4P32


SECT. Scale

Reinforce
Reinforce
Rock, etc.
Masonry


Designed by J. N. FLEWELL
Drawn by M. BARBER
Traced by —
Checked by P. Livingston




ELEVATION
1/8" = 1'-0"



SECTION A-A
Scale: 1/8" = 1'-0"



SECTION B-B
Scale: 1/8" = 1'-0"



DETAIL A-A
Scale: 1/8" = 1'-0"

Reinforcing Steel
Reinforcing Steel shall be 3" clear unless shown otherwise.
No. 4 anchors 3' 0" long, both ways in both flanges.
Minimum size of all reinforcing bars #24 and 24mm.

REQUAWNET FOND



CONWAY, NEW HAMPSHIRE

REINFORCING STEEL


NEW HAMPSHIRE WATER BOARD
- CONCORD, N.H.

Sheet 1010
45 MAY 1961

Sheet 2 of 3



SECTION B-B
5'-0" x 1'-0"



WALKWAY SECTION
1'-0" x 1'-0"

47.02

PEQUAWKET POND DAM

CONWAY, NEW HAMPSHIRE

REINFORCING STEEL


NEW HAMPSHIRE WATER RESOURCES BOARD

- CONCORD, N. H. -

Sheet 2 of 3
As Noted

Sheet 2 of 3


Oct 1969



PLAN OF DAM

Scale: $\frac{1}{4}" = 1'-0"$


NOTE: Assume crest of old dam to Elevation 100.00 and use this as reference.



ELEVATION OF DAM

Scale: $\frac{1}{4}" = 1'-0"$


Designed by J. H. Smith
 Drawn by J. H. Smith
 Traced by J. H. Smith
 Checked by J. H. Smith



SITE LOCATION


Scale: 1" = 500'

If old dam to be at
I use this elevation




PLAN OF PIER

Scale: 1/4" = 1'-0"



ELEVATION OF PIER

Scale: 1/4" = 1'-0"



PLAN OF PROPOSED DAM

NOTE: ELEVATIONS REFER TO NEW HAMPSHIRE
WATER RESOURCES BOARD DATUM, TOP
OF FLASHBOARD ELEVATION + 100.00.
TO CONVERT TO ASSUMED NGVD (USGS
QUAD SHEET NORMAL POOL ELEVATION
458) ADD 358.0 TO ALL ELEVATIONS
THIS SHEET.

SEA CONSULTANTS INC.
US ARMY CORP

JUNE 1980

PEQUANNET POND


Conway, New Hampshire

GENERAL PLANS & ELEV

NEW HAMPSHIRE WATER RESOURCES BOARD
CONCORD, N. H.


Scale:
as noted

Sheet No. 1 of 3



SITE LOCATION

Scale: 1" = 50'



NOTE: ELEVATIONS REFER TO NEW HAMPSHIRE WATER RESOURCES BOARD DATUM, TOP OF FLAGBOARD ELEVATION = 100.00. TO CONVERT TO ASSUMED NGVD (USGS QUAD SHEET NORMAL POOL ELEVATION = 458) ADD 358.0 TO ALL ELEVATIONS THIS SHEET.

SEA CONSULTANTS INC.
US ARMY CORP

JUNE 1960

PEQUANNET POND DAM

Lowway, New Hampshire

GENERAL PLANS & ELEVATIONS

NEW HAMPSHIRE WATER RESOURCES BOARD
- CONCORD, N. H. -

Scale:
as noted

Sheet No. 1 of 3

Date:
9/26/69

APPENDIX C
SELECTED PHOTOGRAPHS






Photo No. 1 - Main Street Bridge and approach channel
to dam



Photo No. 2 - General view of downstream face of dam




Photo No. 3 - View of crest of dam and right abutment
from left abutment



Photo No. 4 - View of downstream face of left abutment



Photo No. 5 - Closeup of leakage between left training wall and left abutment



Photo No. 6 - Closeup of crack at top of right training wall





Photo No. 7 - Building immediately downstream of right abutment



Photo No. 8 - General view of downstream channel from service bridge

APPENDIX D

HYDROLOGIC AND HYDRAULIC COMPUTATIONS



CLIENT Farm Corps JOB NO. 214-7901 PAGE 1 of 31
PROJECT 224 Quaker Power Co. Dam COMPTD. BY RJP DATE 6/1/00
DETAIL Hydrologic Calculations CK'D. BY KMS DATE 7/25/01

I. Basic Data

A. Drainage Area

1. 27.2 square miles — as defined on U.S.G.S chart and then planimeted
2. drainage area would classify as mountainous, however there are numerous ponds and swampy areas upstream from the dam

B. Dam and Storage Information

1. Size Classification : INTERMEDIATE based on Storage (≥ 1000 acre-feet and $< 50,000$ acre-feet)
as indicated below storage at crest of dam estimated to be 1,880 acre-feet

2. Hazard Potential: Significant

3. Storage Information

Descriptive Information	Elevation (feet)	Surface Area (acres)	Storage (acre-feet)
480' contour	480	675	
Top of dam	464.5	335	1,880
460' contour	460	202	635
Normal pool	≈ 459	143	200
Spillway crest	457.3	122	175

CLIENT ES&M Corp JOB NO. 274-7901 PAGE 2 of 21
PROJECT Poquonnet Power Co. Dam COMPTD. BY BWP DATE 6/11/90
DETAIL Hydrologic Calcs CK'D. BY 111 DATE 7-27-90

- * Notes :
- (1) elevations : NGVD
 - (2) Normal pool taken to correspond with pool shown on U.S.G.S. sheet, elevation of top of slopes - 457.3'
 - (3) Surface area at top of dam determined by interpolating between the surface areas defined by the pool shown on the USGS sheet and the 460 feet and 450 feet contours
 - (4) Storage at crest of stoplogs estimated by dividing pooling area into pyramidal trapezoid sections and determining the volume of each section with the equation for the volume of a pyramidal trapezoid

C. Spillway Information

1. Concrete stop log spillway with six stoplog bays located in center of dam.
- 2 discharge over spillway given by sharp-crested weir formula up to elevation 463.0 feet

$$Q = CLH^{3/2} \quad (\text{Standard Handbook for CE's, etc.})$$

where : Q = discharge, cfs
 L = weir length, feet
 H = head over weir, feet
 C = discharge coeff.

$$C = 3.27 + 0.4 \frac{H}{P}$$

where H is as defined above
and P = height of weir
above spillway crest

CLIENT Franklin County JOB No. 274-7901 PAGE 2 of 21
PROJECT Franklin County Dam Project COMPTD. BY BUP DATE 5/11/90
DETAIL Hydrologic Data CK'D. BY AMS DATE 7/23/92

3. above elevation 463.0 feet (bottom of service bridge)
stoplog bay openings will essentially function as
orifices, therefore the orifice discharge formula
would be applicable

$$Q = C a \sqrt{2gh} \quad (\text{Standard Handbook for Engineers})$$

where: Q = discharge, cfs
 C = orifice coeff., use 0.6
 a = area of orifice, ft^2
 g = acceleration due to gravity, ft/s^2
 h = head above horizontal centerline
of orifice, ft

II Estimate Effect of Surcharge Storage on Maximum Probable Discharge

A. Develop stage-discharge curve for outflow from dam complex

1. define sources of outflow

2. discharge over spillway - assume stage set at approx 457.3' ("typical" stoplog arrangement)

(1) discharge to elevation 463 defined by surcharged weir formula as defined above

(2) discharge above elevation 463' defined by orifice discharge equation for stoplog bay openings

(3) discharge over service orifice across weir above elevation 464.5' defined by orifice discharge weir equation

$$Q = CLH^{3/2} \quad \text{with } C = 2.3$$

CLIENT Ames Corp JOB NO. 224-7001 PAGE 1 of 3
PROJECT Hydroelectric Power Plant COMPTD. BY ELP DATE 7/23/80
DETAIL Hydroelectric Cycles CK'D. BY KMS DATE 7/23/80

a. discharge over training walls and abutments
above elevation 464.5', defined by concrete
crested weir section with $C=2.6$

2. Discharge over spillway

a. Weir discharge

Elevation (feet NGVD)	C	L (feet)	H (feet)	Q (cfs)
457.3	—	—	—	—
458	3.29	30.8	0.7	60
459	3.40	↓	1.7	230
460	3.47	↓	2.7	470
461	3.55	↓	3.7	730
462	3.62	↓	4.7	1140
463	3.70	↓	5.7	1550

b. Orifice discharge

Elevation (feet, NGVD)	C	a (feet ²)	h (feet)	Q (cfs)
464	0.6	≈ 176	3.9	1,670
465	↓	↓	4.9	1,880
466	↓	↓	5.9	2,060
467	↓	↓	6.9	2,230
468	↓	↓	7.9	2,380
469	↓	↓	8.9	2,530
470	↓	↓	9.9	2,670

3. Discharge over service bridge

Elevation (feet NGVD)	C	L (feet)	H (feet)	Q (cfs)
464.5	2.8	≈ 37	0	0
465	↓	↓	0.5	40
466	↓	↓	1.5	110

CLIENT Essex Corp. JOB No. 224-7901 PAGE 5 of 21
PROJECT Downsview Dam Co. Turn COMPTD. BY BWP DATE 5/11/90
DETAIL Hydrologic Calc. CK'D. BY KMS DATE 7-25-90

3. Service bridge discharge - CONTINUED

Elevation (feet NGVD)	C	L	H	Q
467	2.8	≈ 37	2.5	410
468	↓	↓	3.5	690
469			4.5	990
470			5.5	1340

4. Discharge over left training wall and abutment

Elevation (feet NGVD)	C	Effective L (feet)	Avg H (feet)	Q cfs
464.5	2.6	—	0	0
465	↓	20	0.25	7
466		90	0.75	150
467		290	1.25	1050
468		490	1.75	2950
469		690	2.25	6,050
470	↓	890	2.75	10,600

5. Discharge over right training wall and abutment

Elevation (feet NGVD)	C	Effective L (feet)	Avg H (feet)	Q cfs
464.5	2.6	—	0	0
465	↓	10	0.25	3
466		80	0.75	120
467		235	1.25	1030
468		490	1.75	2950
469		645	2.25	6,000
470	↓	900	2.75	10,700

SIEIA CONSULTANTS INC.
ENGINEERS / PLANNERS

BOSTON, MASS.
ROCHESTER, N.H.


CLIENT Green Corps JOB NO. 224-2201 PAGE 21
PROJECT Pegawet River G. Dam COMPTD. BY BWP DATE 6/1/80
DETAIL Hydrologic Calc. CK'D. BY AMS DATE 7/25/82

6. Total Discharge from project site

Elevation (feet NGVD)	Q Spillway	Q Service outlet	Q Leak out	Q Right about	Q TOTAL
457.3	0	0	0	0	0
458	60	↑	↑	↑	60
459	230	↑	↑	↑	230
460	470	↑	↑	↑	470
461	790	↑	↑	↑	790
462	1,140	↑	↑	↑	1,140
463	1,550	↑	↑	↑	1,550
464	1,670	0	0	0	1,670
465	1,930	40	7	3	1,980
466	2,060	20	150	30	2,530
467	2,230	50	1,050	1,030	4,720
468	2,380	690	2,950	2,950	8,960
469	2,530	990	6,050	6,100	15,670
470	2,670	1,340	10,600	10,700	25,310

FIGURE 1

DISCHARGE vs. ELEVATION



CLIENT <u>Army Corps</u>	JOB NO. <u>274-7987</u>	PAGE <u>8 of 21</u>
PROJECT <u>Sagunawet Power Co Dam</u>	COMPTD. BY <u>BWD</u>	DATE <u>6/11/80</u>
DETAIL <u>Hydrologic Calcs</u>	CK'D. BY <u>KMS</u>	DATE <u>7/25/80</u>

3. Effect of surcharge storage on max. prob. discharge

1. Pertinent Data

- Drainage area = 27.2 square miles
- Characteristics of basin - mountainous, however use rating curve to estimate MPF Peak Flow Rate due to numerous lakes and swampy areas located in upper part of basin
- Test flood = $1/2$ PMF
- Follow Army Corps' procedure

2. STEP 1: Determine Peak Inflow Q_{p1} from Guide Curve

- the maximum probable discharge was estimated to be 1350 cfs/sq.mi

$$\therefore \text{PMF} = (27.2 \text{ sq.mi}) (1350 \text{ cfs/sq.mi})$$

$$\approx 36,700 \text{ cfs}$$

$$1/2 \text{ PMF} \approx 18,400 \text{ cfs}$$

3. STEP 2: Determine surcharge height to pass Q_{p1} , $STOR_1$, and Q_{p2}

- from Figure 1 determine surcharge height to pass

$$Q_{p1} = 18,400 \text{ cfs}$$

$$\begin{aligned} \text{surcharge elevation} &\approx +60.3 \text{ ft} \\ \text{elev. spillway stoplogs} &= +57.3 \text{ ft} \\ \text{surcharge height} &= 12.0 \text{ feet} \end{aligned}$$

- determine volume of surcharge $STOR_1$ in inches of runoff


First determine volume of storage in base unit of inches of runoff

(1) determine surface area of spillway and approach
surcharge elevation from Figure 2 $\approx 425 \text{ ac-ft}$

(2) determine average surface area of storage area
surcharge elevation from Figure 2 $\approx 425 \text{ ac-ft}$

FIGURE 2

POND SURFACE AREA VS ELEVATION



ELEVATION (feet)

SURFACE AREA (acres)

SIEIA CONSULTANTS INC.
ENGINEERS / PLANNERS

BOSTON, MASS.
ROCHESTER, N.H.

CLIENT Army Corps JOB No. 274-7901 PAGE 20-21
PROJECT Bennington Power Co. Dam COMPTD. BY BWP DATE 6/11/83
DETAIL Hydrologic Calcs CK'D. BY WJS DATE 7-3/83

3. multiply each average area by average
portion of surcharge height

$$STOR_1 = \frac{\text{Volume of storage (as acre-inches)}}{\text{drainage area}}$$

$$STOR_1 = \frac{[(2.74) \left(\frac{122 \text{ acres} + 202 \text{ acres}}{2} \right) + (9.24) \left(\frac{202 \text{ ac} + 425 \text{ ac}}{2} \right)] (2.31 \text{ ft})}{(27.2 \text{ sq mi}) (640 \text{ acres/sq mi})}$$

$$STOR_1 = 2.31 \text{ inches}$$

c. determine Q_{P2}

$$Q_{P2} = Q_{P1} \left(1 - \frac{STOR_1}{9.5"} \right)$$

$$Q_{P2} = (18,400 \text{ cfs}) \left(1 - \frac{2.31}{9.5"} \right)$$

$$Q_{P2} \approx 13,900 \text{ cfs}$$

4. STEP 3: Determine surcharge height and $STOR_2$ to pass Q_{P2} and then Q_{P3}

a. From Figure 1 determine surcharge height to pass

$$Q_{P2} = 13,900 \text{ cfs}$$

$$\text{Surcharge elevation} \approx 469.3 \text{ ft}$$

$$\text{2001 Spillway Storage} = 457.3 \text{ ac-ft}$$

$$\text{Surcharge height} = 1.5 \text{ ft}$$

$$\text{Surfact area @ surcharge height} \approx 1.5 \text{ ft}$$

AD-A156 416

NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
PEQUAMKET POWDER COMP. (U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV JUN 80


2/2

UNCLASSIFIED

F/G 13/13

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

CLIENT Army Corps
PROJECT Powassunk Power Co. Dam
DETAIL Hydrologic Calcs.

JOB NO. 274-7901 PAGE 11 of 21
COMPTD. BY BWP DATE 6/11/80
CK'D. BY KMS DATE 7/23/80

b. determine $STOR_2$

$$STOR_2 = \frac{[437ac + (8.9ft)(\frac{202ac + 410ac}{2})](12"/ft)}{(27.2 sq.mi)(640 ac/sq.mi)}$$

$$= 2.16 \text{ inches}$$

c. Average $STOR_1$ and $STOR_2$

$$STOR_{AVG} = \frac{STOR_1 + STOR_2}{2}$$

$$STOR_{AVG} = \frac{2.31 \text{ in} + 2.16 \text{ in}}{2}$$

$$STOR_{AVG} = 2.23 \text{ in}$$

d. determine Q_{p3}

$$Q_{p3} = (18,400 \text{ cfs}) \left(1 - \frac{2.23"}{9.5"}\right)$$

$$Q_{p3} = 14,100 \text{ cfs}$$

5. STEP 4: Determine surcharge height for Q_{p3} and $STOR_3$

a. from Figure 1 surcharge height for $Q_{p3} = 14,100 \text{ cfs}$

$$\begin{aligned} \text{Surcharge elevation} &\approx 463.9 \text{ ft} \\ \text{elev. spillway stop logs} &= 457.3 \text{ ft} \\ \text{surcharge height} &= 11.5 \text{ ft} \end{aligned}$$

Surface area at surcharge elev $\approx 410 \text{ acres}$

b. determine $STOR_3$

$$STOR_3 = \frac{[437ac + (8.9ft)(\frac{202ac + 410ac}{2})](12"/ft)}{(27.2 sq.mi)(640 ac/sq.mi)}$$

SIEIA CONSULTANTS INC.
ENGINEERS / PLANNERS

BOSTON, MASS.
ROCHESTER, N.H.

CLIENT <u>Army Corps</u>	JOB NO. <u>274-7901</u>	PAGE <u>12 of 31</u>
PROJECT <u>Pegueset Power Co Dam</u>	COMPTD. BY <u>BWP</u>	DATE <u>6/11/80</u>
DETAIL <u>Hydrologic Calcs</u>	CK'D. BY <u>KMS</u>	DATE <u>7/23/80</u>

$$STOR_3 = 2.16 \text{ inches}$$

c. determine $STOR_{AVG}$

$$STOR_{AVG} = \frac{2.23 \text{ in} + 2.16 \text{ in}}{2}$$

$$STOR_{AVG} = 2.20 \text{ inches}$$

d. determine Q_{p4}

$$Q_{p4} = (18,400 \text{ cfs}) \left(1 - \frac{2.20}{9.5} \right)$$

$$Q_{p4} = 14,100 \text{ cfs}$$

6. STEP 5: Determine surcharge height for Q_{p4} and $STOR_4$

a. From Figure 1 surcharge height for $Q_{p4} = 14,100 \text{ cfs}$

$$\begin{aligned} \text{surcharge elevation} &\approx 469.9 \text{ ft} \\ \text{elev. spillway stop logs} &= 457.3 \text{ ft} \\ &\hline &11.5 \text{ feet} \end{aligned}$$

surface area @ surcharge elev $\approx 410 \text{ acres}$

b. determine $STOR_4$

$$STOR_4 = \frac{[437 \text{ ac} + (9.84) \left(\frac{202 \text{ ac} + 410 \text{ ac}}{2} \right)] (12 \text{ in/ft})}{(27.2 \text{ sq. mi.}) (640 \text{ ac/sq. mi.})}$$

$$STOR_4 = 2.18 \text{ inches}$$

c. determine $STOR_{AVG}$

$$STOR_{AVG} = \frac{2.21 \text{ in} + 2.18 \text{ in}}{2}$$

$$= 2.19 \text{ inches}$$

CLIENT Army Corps JOB No. 274-7901 PAGE 2 of 2
PROJECT Pegueset Power Co. Dam COMPTD. BY BWP DATE 6/13/90
DETAIL Hydrologic Calcs CK'D. BY KMS DATE 7/25/90

STOR₄ and STOR_{AVG} agree to within 1%, therefore
accept routed test flood outflow equal to 14,100 cfs
at a surcharge elevation of 468.9 feet

7 In Conclusion

- a. The routed test flood outflow of 14,100 cfs
will over top the dam by approximately 4.3 feet
- b. Spillway Capacity - with stoplogs set at
design crest elevation of 457.3 feet

(1) Water surface at crest of dam - 464.5 feet
(use orifice discharge equation per previous discussion)

$$Q = (0.6)(176 \text{ ft}^2) \left[(2)(32.2)(464.5' - 460.1') \right]^{1/2} \approx 1,780 \text{ cfs}$$

(2) Water surface at test flood elevation - 468.9 feet

(a) discharge through stoplog bay

$$Q = (0.6)(176 \text{ ft}^2) \left[(2)(32.2)(468.9 - 460.1') \right]^{1/2} \approx 2,500 \text{ cfs}$$

(b) discharge over service bridge

$$Q = (2.8)(37 \text{ ft}) (468.9' - 464.5')^{3/2} \approx 920 \text{ cfs}$$

$$c) Q_{\text{total}} = 2,500 \text{ cfs} + 920 \text{ cfs} = 3,420 \text{ cfs}$$

CLIENT Arrow Corp JOB NO. 274-7901 PAGE 14 of 21
PROJECT Conduit Sewer System COMPTD. BY BWP DATE 6/13/90
DETAIL Hydrologic Calc CK'D. BY JMS DATE 7/5/90

III. Using "Rule of Thumb" Guidance for Estimating Downstream Failure Hydrographs examine impact of dam failure

A. Since spillway length is large compared to length of dam, the tailwater resulting from discharge over the spillway with the water surface at the crest of dam may be significant

1. from previous calcs. steady state discharge over spillway with water surface at crest of dam $\approx 1,780$ cfs (p.D-14 of the Hydrologic Calcs).

2. Using Stage - Discharge curve prepared for routing of failure discharge determine stage for steady state discharge

a. Reach 1 - from Figure 3 Stage ≈ 8.0 feet

b. Reach 2 - from Figure 3 Stage ≈ 6.2 feet

3. The failure discharge should now be computed and routed through the stream reaches using the "Rule of Thumb" Guidance for Estimating Downstream Failure Hydrographs.

If the hazard is significantly increased by the failure discharge then the hazard classification will be defined by this routing procedure. If there is no significant increase in hazard over the steady state discharge, then the hazard classification shall be determined by routing the failure discharge through the crest.

CLIENT Army Corps JOB NO. 274-7901 PAGE 15 of 21
PROJECT Peabody Dam COMPTD. BY RWP DATE 7/23/90
DETAIL Hydraulic Calc CK'D. BY KMS DATE 7/25/90

B. Reach 1

1. STEP 1: Determine reservoir storage at time of failure

from previous calcs storage $\approx 1,990$ ac-ft

2. STEP 2: Determine Peak Failure Outflow, Q_p

$$a. Q_p = (8/27) W_b g^{1/2} Y_o^{3/2}$$

where W_b = Breach Width (max 40% of dam length)
= $(0.4)(45 \text{ feet})$
= 18 feet

width of each section of spillway equals 17.4 feet, thus assume width of 3 sloping bays

Y_o = Total height from channel bottom to pool level at failure
= $464.5' - 452.5'$ (crest elevation)
= 12 feet

$$Q_p = (8/27) (17.4 \text{ feet}) (32.2)^{1/2} (12 \text{ feet})^{3/2}$$

$$\approx 1,220 \text{ cfs}$$

- b. must add discharge over unfilled portion of spillway to the failure discharge

$$Q_{\text{unfilled}} = \frac{1}{2} \left(\text{spillway discharge over unfilled portion of spillway} \right)$$

$$= \frac{1}{2} (1790 \text{ cfs})$$

$$= 895 \text{ cfs}$$

$$c. Q_{\text{TOTAL}} = 1,220 \text{ cfs} + 895 \text{ cfs}$$

$$= 2,115 \text{ cfs}$$

SIEIA CONSULTANTS INC.
ENGINEERS / PLANNERS

BOSTON, MASS.
ROCHESTER, N.H.

CLIENT <u>Army Corps</u>	JOB NO. <u>274-7901</u>	PAGE <u>16 of 21</u>
PROJECT <u>Washburn Dam Co Dam</u>	COMPTD. BY <u>BWP</u>	DATE <u>7/23/80</u>
DETAIL <u>Hydrologic Calcs.</u>	CK'D. BY <u>KMS</u>	DATE <u>7/25/80</u>

STEP 3: Prepare stage-discharge curve for Reach 1

a. Pertinent Data

- (1) Reach length = 100 feet
- (2) Channel slope = 0.0016
- (3) Manning n = 0.06
- (4) Channel shape - trapezoidal
- (5) Base width \approx 45 feet

b. See Figure 3 for stage-discharge curve.

STEP 4: Estimate Reach Outflow

- a. Determine stage for $Q_{p1} = 2,110 \text{ cfs}$ from Figure 3
and find volume in reach

- (1) Stage (depth of flow) = 0.3 feet (Total Stage = 3.3 feet)
above pre-failure discharge

- (2) Volume in reach = (reach length) (cross-sectional area of channel)

$$\begin{aligned} \text{X-area} &= (0.5)(0.3 \text{ ft})(67 \text{ ft} + 69 \text{ ft}) \\ &= 54 \text{ ft}^2 \end{aligned}$$

$$\begin{aligned} \text{Volume} = V_1 &= \frac{(54 \text{ ft}^2)(100 \text{ ft})}{43,560 \text{ ft}^2/\text{acre}} \\ &= 0.12 \text{ acre-ft} \end{aligned}$$

$$V_1 < \frac{S}{2} \therefore \text{reach length OK}$$

b. Determine $Q_{PZ}(\text{TRIAL})$

$$Q_{PZ}(\text{TRIAL}) = Q_{P1} \left(1 - \frac{V_1}{S}\right)$$

$$Q_{PZ}(\text{TRIAL}) = (2,110 \text{ cfs}) \left(1 - \frac{0.12 \text{ acre-ft}}{1,380 \text{ acre-ft}}\right)$$

$$Q_{PZ}(\text{TRIAL}) = 2,110 \text{ cfs}$$

CLIENT Army Corps JOB NO. 274-7901 PAGE 2 of 21
PROJECT Pequabets River Co. Dam COMPTD. BY BWP DATE 2/23/90
DETAIL Hydrologic Calcs. CK'D. BY KMS DATE 7/25/90

c. Compute V_2 using $Q_{P2}(\text{TRIAL})$

From Figure 3 determine stage for $Q_{P2}(\text{TRIAL})$

Stage = 0.8 feet (Total Stage = 3.3 feet)
above pre-failure discharge

X-area = (0.5)(0.8 feet)(67 ft + 69 ft)
= 54 ft²

$$V_2 = \frac{(54 \text{ ft}^2)(100 \text{ ft})}{43,560 \text{ ft}^2/\text{acre}}$$

$$V_2 = 0.12 \text{ acre-ft}$$

d. Average V_1 and V_2 and compute Q_{P2}

$$(1) V_{\text{avg}} = \frac{V_1 + V_2}{2}$$

$$V_{\text{avg}} = \frac{0.12 \text{ ac-ft} + 0.12 \text{ ac-ft}}{2}$$

$$V_{\text{avg}} = 0.12 \text{ ac-ft}$$

$$(2) Q_{P2} = Q_{P1} \left(1 - \frac{V_{\text{avg}}}{S} \right)$$

$$Q_{P2} = (2,110 \text{ cfs}) \left(1 - \frac{0.12}{1,930} \right)$$

$$Q_{P2} = 2,110 \text{ cfs}$$

CLIENT Army Corps JOB No. 294-7901 PAGE 19 of 21
PROJECT Dugananket Power Plant COMPTD. BY BWP DATE 7/23/90
DETAIL Hydrologic Calcs. CK'D. BY KMS DATE 7/25/90

C. Reach 2

STEP 3: Prepare stage-discharge curve for Reach 2

a. Pertinent Data

- (1) Reach length = 500 feet
- (2) Channel slope = 0.0016
- (3) Manning n = 0.06
- (4) Channel shape - trapezoidal
- (5) Base width \approx 45 feet

b. See Figure 3 for stage-discharge curve

STEP 4: Estimate Reach Outflow

- a. Determine stage for $Q_{P2} = 2,110 \text{ cfs}$ from Figure 3
and find volume in reach

- (1) Stage (depth of flow) = 0.3 ft (Total Stage = 6.5 ft)
above pre-failure discharge

- (2) Volume in reach = (reach length) (cross-sectional area of channel)

$$\text{X-area} = (0.5)(0.3 \text{ ft})(630 \text{ ft} + 635 \text{ ft}) \\ \approx 197 \text{ ft}^2$$

$$\text{Volume} = V_1 = \frac{(197 \text{ ft}^2)(500 \text{ ft})}{43,560 \text{ ft}^2/\text{acre}}$$

$$= 2.3 \text{ acre-feet}$$

$$V_1 < \frac{S}{2} \therefore \text{reach length OK}$$

b. Determine $Q_{P3}(\text{TRIAL})$

$$Q_{P3}(\text{TRIAL}) = Q_{P2} \left(1 - \frac{V_1}{S}\right)$$

$$Q_{P3}(\text{TRIAL}) = (2,110 \text{ cfs}) \left(1 - \frac{2.3}{19.5}\right)$$

$$Q_{P3}(\text{TRIAL}) = 2,110 \text{ cfs}$$

CLIENT Army Corps JOB No. 274-7901 PAGE 19 of 21
PROJECT Designing + Power Gen. Station COMPTD. BY BWP DATE 7/23/90
DETAIL Hydrologic Calcs CK'D. BY KMS DATE 7/23/90

c. Compute V_2 using $Q_{P3}(\text{TRIAL})$

From Figure 3 determine stage for $Q_{P3}(\text{TRIAL})$

Stage = 0.3 ft (Total stage = 6.5 ft)
above pre-failure discharge

$$X\text{-area} = (0.5)(0.3 \text{ ft})(630 \text{ ft} + 695 \text{ ft}) \\ \approx 197 \text{ ft}^2$$

$$V_2 = \frac{(197 \text{ ft}^2)(500 \text{ ft})}{43,560 \text{ ft}^2/\text{acre}}$$

$$V_2 = 2.3 \text{ acre-ft}$$

d. Average V_1 and V_2 and compute Q_{P3}

$$(1) V_{\text{avg}} = \frac{V_1 + V_2}{2}$$

$$V_{\text{avg}} = \frac{2.3 \text{ acre-ft} + 2.3 \text{ acre-ft}}{2}$$

$$V_{\text{avg}} = 2.3 \text{ acre-ft}$$

$$(2) Q_{P3} = Q_{P2} \left(1 - \frac{V_{\text{avg}}}{S}\right)$$

$$Q_{P3} = (2,110 \text{ cfs}) \left(1 - \frac{2.3}{1980}\right)$$

$$Q_{P3} = 2,110 \text{ cfs}$$


CLIENT <u>Army Corps</u>	JOB NO. <u>274-790</u>	PAGE <u>21 of 21</u>
PROJECT <u>Dam and Flood Control</u>	COMPTD. BY <u>RLS</u>	DATE <u>7/7/80</u>
DETAIL <u>Failure Discharge</u>	CK'D. BY <u>KMS</u>	DATE <u>7/23/80</u>

2. Conclusions - from failure discharge routing

1. Reach 1 - The addition of the failure discharge will increase the stage in this reach by about 1 foot above that for the pre-failure flow. This increase in stage will result in water rising to the sill level of the building located near the right abutment. The pre-failure discharge was about 1 foot below the sill.
2. Reach 2 - Downstream from Reach 1 the stream channel profile broadens considerably. Consequently, there is very little difference between the stage of the failure discharge and the pre-failure flow, since a relatively small increase in stage results in a significant increase in discharge. No significant damage would result in Reach 2.
3. Although the increase in stage in Reach 1 is not large, it does result in water reaching the sill level of the building located near the right abutment. Consequently, the hazard would increase significantly due to the potential for economic loss. Therefore, the hazard classification for the Penobscot Company Dam has been determined from this previous analysis.

FIGURE 3

DISCHARGE vs STAGE



APPENDIX E

INFORMATION AS CONTAINED IN
THE NATIONAL INVENTORY OF DAMS

END

FILMED

8-85

DTIC